

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT		
2.855	2.93	DASH	DASH		55.
2.93	3.02	DASH	SOLID		594.
3.02	3.11	SOLID	SOLID		950.
3.11	3.23	DASH	SOLID		792.
3.23	3.44	SOLID	SOLID		2218.
3.44	3.53	SOLID	DASH		594.
3.53	3.57	DASH	DASH		53.
3.57	3.68	DASH	SOLID		726.
3.68	4.26	SOLID	SOLID		6125.
4.26	4.327	SOLID	DASH		442.
				SUB TOTAL	12,549.

ASSUME 50% LOSS DURING SHIMMING

4" YELLOW EST - $150\% \times 12,549 = 18,824' LF$

ALTHOUGH NOT SHOWN ON THIS SHEET,
THE $\&$ SHALL BE BROKEN AT ALL TOWN-
HIGHWAYS AS SHOWN ON DETAIL SHEET

TEMPORARY 4" REFLECTORIZED WHITE LINE

4" WHITE EDGE LINES - PROJ LENGTH X 2

$7601 \times 2 = 15,202' LF$