PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	GRAVEL SHOULDERS	GRAVEL SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	CHANGE ELEV. OF CB, DI, OR MH	ALL PURPOSE EXC. RENTAL	POWER BROOM RENTAL	ENFORCED TRAFFIC OFFICERS	FLAGPERSONS	MOBILIZATION	TEMPORARY PAVEMENT MARKING- White	TEMPORARY PAVEMENT MARKING- Yellow	REMARKS
						OPTION										
ITEM NUMBER					402.10	402.11	404.65	406.25	604.40	608.25	608.30	630.10	630.15	635.10	646.35	646.36
UNIT	FEET	FT	INCH	S.Y.	CY	TON	CWT	TON	EA	HR	HR	HR	HR	LS	LF	
LOCATION																
MIDDLEBURY MM 0.000-MM6.58																
BRISTOL 0.00 - 0.60	36889	22	3/4		2049	3381	227	3757								250 T/M Level
-1056' for bridge const.								1746								
BRISTOL MM 0.60-1.05	2376	24	3/4		264	436	16	264								
								122								250 T/M Level Factored 273 T/M
BRISTOL MM 1.05-5.75	24816	22	3/4		1380	2278	153	2528								
								1175								
BRISTOL MM 5.75-6.025	1452	36	3/4		81	133	15	242								250 T/M Level Factored 409 T/M
								113								
PROJECT ESTIMATE					300	495		300	1	10	95	258	258	1	125918	187381
ROUNDING					26	77	9	53			5	2	2	==	82	19
					4100	6800	420	10300	1	10	100	260	260	1	126000	187400

HMA 2465

PROJECT MIDDLEBURY-BRISTOL NUMBER HMA 2518 SHEET 4 OF 11