PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	GRAVEL SHOULDERS	GRAVEL SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	CHANGE ELEV. OF CB, DI, OR MI	ALL PURPOSE EXC. RENTAL, TYPE I	POWER BROOM RENTAL	UNIFORMED TRAFFIC OFFICERS	FLAGPERSONS	MOBILIZATION	TEMPORARY PAVEMENT MARKING- White	TEMPORARY PAVEMENT MARKING- Yellow	REMARKS
ITEM NUMBER				402.10	402.11	406.65	406.25	604.40	608.25	608.30	630.10	630.15	635.10	646.35	646.36	
UNIT	FEET	FT	INCH	S.Y.	CY	TON	CYT	TON	EA	HR	HR	HR	HR	LS	LF	
LOCATION																
DUMMERSTON MM 0.00-MM 3.69	19482	24	1¼				131	3608								1¼" WEARING COURSE
								604								164 TON/MI. LEVEL
		4	1¼				44	1203								4' PAVED SHOULDER
MM 3.69 - MM 5.287	8431	24	1¼				57	1561								1¼" WEARING COURSE
								261								164 TON/MI. LEVEL
		8	1¼				38	1041								8' PAVED SHOULDERS
PROJ. EST. DRIVES & APPROACH					250	412	5	150								
PROJECT									1	1	43	207	207	1	55862	72485
SUB-TOTAL					250	412	275	8428	1	1	43	207	207	1	55862	72485
ROUND					–	–	5	22	–	–	2	3	3	–	–	15
TOTAL	27913				250	412	280	8450	1	1	45	210	210	1	55862	72500

PROJECT DUMMERSTON NUMBER RS 0113(37) SHEET 13 OF 20