

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT	QUANTITY CL	QUANTITY RT	TOTAL
0.00	1.73	SOLID	SOLID	9134.		9134.	18268.
1.73	1.89	DASH	SOLID	211.		845.	1056.
1.89	2.52	SOLID	SOLID	3326.		3326.	6652.
2.52	2.64	SOLID	DASH	634.		158.	792.
2.64	2.67	SOLID	SOLID	158.		158.	316.
2.67	2.81	DASH	SOLID	185.		739.	924.
2.81	3.16	SOLID	SOLID	1848.		1848.	3696.
3.16	3.25	SOLID	DASH	475.		119.	594.
3.25	3.30	DASH	DASH		66.		66.
3.30	3.48	DASH	SOLID	238.		950.	1188.
3.48	3.49	DASH	DASH		13.		13.
3.49	3.68	SOLID	DASH	1003.		251.	1254.
3.68	3.90	DASH	DASH		290.		290.
3.90	3.95	DASH	SOLID	66.		264.	330.
3.95	4.29	SOLID	SOLID	1795.		1795.	3590.
4.29	4.43	SOLID	DASH	739.		185.	924.
4.43	4.45	SOLID	SOLID	106.		106.	212.
4.45	4.64	DASH	SOLID	251.		1003.	1254.
4.64	5.29	SOLID	SOLID	3432.		3432.	6864.
				23601.	369.	24313.	48283.

ASSUME 50% LOST DUE TO LEVELING

$$48283 \times 0.5 = 24142$$

24142.

72425.

ROUND

75.

PROJECT EST.

72500

ALTHOUGH NOT SHOWN ON THIS SHEET, THE CENTERLINE SHALL BE BROKEN AT ALL TOWN HIGHWAY INTERSECTIONS AS SHOWN ON THE PLAN DETAIL SHEET.

TEMPORARY 4"- REFLECTORIZED WHITE LINE

0.00	5.29	SOLID	SOLID	27931.		27931.	55862.
					DUMMERSTON		
						CHEET	14-25-20