

QUANTITY SHEET 1985 STATEWIDE SAFETY PROJECT

APPROXIMATE SUMMARY OF QUANTITIES

STATEWIDE M SFTY (85)			STATEWIDE RS SFTY (85)				STATEWIDE F SFTY (85)													COMPOSITE TOTAL	UNIT	ITEMS	ITEM NO.
WILLISTON	BRATTLEBORO	M SFTY (85) TOTALS	WORCESTER	WEATHERSFIELD-WINDSOR	RS SFTY (85) ROUNDINGS	RS SFTY (85) TOTAL	ALBURG	ENOSBURG	LOWELL-WESTFIELD	LUDLOW-MT. HOLLY-SHREWSBURY	SO. BURLINGTON	BERLIN-BARRE	NEW HAVEN	MENDON-SHERBURN	LUDLOW	JOHNSON	NORTH HERO BRAND ISLE	F SFTY (85) ROUNDING	F SFTY (85) TOTALS				
					3	3												7	7	10	EA	REMOVING SMALL TREES	201.15
					2	2												3	3	5	EA	REMOVING LARGE TREES	201.16
					10	10								5	10			10	25	35	CY	UNCLASSIFIED EXCAVATION	203.17
				160	15	175			20				315	770	10			115	1160	1338	CY	EARTH BORROW	203.30
				25	15	40							27	103	130			30	130	130	CY	GRANULAR BORROW	203.32
				16	4	20							4	131				15	160	200	CY	TRENCH EXCAVATION OF EARTH	204.20
																		15	150	170	CY	TRENCH EXCAVATION OF ROCK	204.21
			260	497	18	775			667	198			10	2615	184	5	338	38	4085	4830	TON	AGGREGATE SHOULDERS	402.12
					25	25										10		25	38	60	TON	BITUMINOUS CONCRETE PAVEMENT	406.25
																		5	5	5	CY	CONCRETE CLASS AA	501.21
								4	1				2	1					8	8	CY	CONCRETE, CLASS A	501.22
				7.0	3.0	10.0								55.0	1.0			4.0	60.0	70.0	CY	CONCRETE, CLASS B	501.25
				700	300	1090			140	20				5700	20			120	6000	7000	LBS	REINFORCING STEEL	507.15
								2	1					1	1				5	5	GAL	WATER REPELLENT	514.10
									1					1	1				3	3	GAL	JOINT SEALER POLYURETHANE	524.20
									198					224	228				670	670	LF	REMOVAL OF EXISTING RAILING	525.10
									209					282	239				730	730	LF	BRIDGE RAILING - 2 RAIL GALV. BOX BEAM	525.31
								100							100				200	200	LF	BRIDGE RAILING - HD STEEL BEAM BEAM / FASCIA MOUNTED	525.41
														1					1	1	EA	PARTIAL REMOVAL OF STRUCTURE	529.20
								5											5	5	CY	REMOVAL OF CONCRETE OR MASONRY	529.25
																		15	15	15	GAL	EPOXY MORTAR COMPOUND	530.30
													16	24					30	30	LF	15" CSP .064	601.0010
				22	22	22							30	50				8	88	110	LF	18" CSP .064	601.0015
													8	26				6	40	40	LF	24" CSP .064	601.0025
													18						18	18	LF	42" CSP .109	601.0052
													16						16	16	LF	48" CSP .109	601.0057
													96						96	96	LF	60" CSP .138	601.0068

DRAWING 3480 3