TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (EA.)	REMOVE (X)	RETAIN (X)	NEW AND SALVAGED SIGNS: NEW "A" (S.F.)	NEW "B" (S.F.)	SALV. SIGN (EA.)	SALV. T.I.S. (S.F.)	EXISTING POSTS: RET.	DRILL	REM.	SALV.	NEW SIGN POSTS: NUMBER OF POSTS	FLANGED CHANNEL: 2.0 LB./FT.	2.5 LB./FT.	3.0 LB./FT.	TUBULAR ALUMINUM: 3.0" Ø	3.0" □	4.0" Ø	4.0" Ø MOD.	W SHAPED STEEL: POST SIZE	WEIGHT	FTG. SIZE 24"	FTG. SIZE 30"	REMARKS	FOR SIGN DETAIL SHEET: PLAN SHEET NUMBER	STD. SHEET NUMBER
2.65 RT			2																									
			3									3																
2.645 RT	* NOTE	18" x 24"				3																				* NOTE		E-19
		18" x 24"				3								1	X											MOUNT ON SINGLE POSTS, BACK TO BACK		E-19
2.655 RT	* NOTE	18" x 24"				3																						E-19
		18" x 24				3								1	X													E-19
2.8 LT	30 MPH				X																							
					X					X																		
2.63 RT		48" x 24"				8								2			X											
2.675 RT		48" x 24"				8								2			X											
2.63 RT		18" x 18"				2.3																						E-19 B
2.675 RT		18" x 18"				2.3																						E-19 B
2.9 LT	* NOTE	30" x 30"	1			6.3				X																SNOWMOBILE CROSSING SIGN IN PLACE DURING WINTER MONTHS ONLY		
3.06 RT		30" x 30"	1			6.3				X																		E-19 A
3.17 LT	* NOTE		1	X																						* NOTE RELOCATE TO 3.185		
			1									1																
3.15 LT		18" x 24"				3								1	X													E-19
3.165 LT		18" x 24				3								1	X													E-19
3.185 LT								1						2	X													
3.23 LT	* NOTE	18" x 18"				2.3																				* MOUNT ON LEFT POST OF ARROW (3.17 LT)		E-19 B
3.26 LT		30" x 30"	1			6.3						1		1														E-19 A
3.8 LT	LEGAL LOAD LIMIT / STOP				X					X																		
		30" x 30"	1			6.3																						E-15 C
3.95 LT		12" x 36"				3								1														
4.0 LT		12" x 36"				3								1														
3.95 RT		12" x 36"				3								1														
4.0 RT		12" x 36"				3								1														
	SUB TOTALS		11			78.1		1																				
	TOTALS		25			138.3		4																				

ITEM NUMBER	ITEM	QUANTITY	RND	UNIT	TOTAL
675.20	TRAFFIC SIGNS, TYPE A	138.3	0.7	S.F.	139
675.30	FLANGED CHANNEL SIGN POSTS	754		LB.	754
675.50	REMOVING SIGNS	25	-	EA.	25
675.60	ERECTING SALVAGED SIGN	4	-	EA.	4

SEE SHEET TD 504 FOR PROJECT SUMMARY OF QUANTITIES AND REVISION NOTE FOR LEGAL LOAD LIMIT SIGNS.

TOTALS

FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".

PREPARED BY D.F. DATE 11 MAR.
CHECKED BY WORCESTER DATE SECTS 1 & 2
PROJ. STATEWIDE NO. RS-SFTY (85)S
TRAFFIC SHEET NO. TD 507 SHEET 34 OF 200

[redacted] 1986