

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS.	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			RC PIPES			M.E.S	RCPES	CONC	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL			TIMBER CURB	ITEM 604.40	SELECTIVE THINNING	GUARD RAIL ITEMS					DELINEATORS	REMARKS
		SMALL	LARGE						D	L	TH	D	L	CL							I	II	621.80				621.20	621.60	621.50				
MT. HOLLY																																	
1.04	RT							49																	40						1	REMOVE EXISTING GUARD RAIL. REPLACE WITH APPROACH SECTION TYPE I AND B.C.T. SEE SHEET 3 FOR DETAILS.	
1.07	RT							49																	40						1	REMOVE EXISTING GUARD RAIL. REPLACE WITH APPROACH SECTION TYPE I AND B.C.T. SEE SHEET 3 FOR DETAILS.	
1.04	LT							49																	40						1	REMOVE EXISTING GUARD RAIL. REPLACE WITH APPROACH SECTION TPYE I AND B.C.T. SEE SHEET 3 FOR DETAILS.	
1.07	LT							51																	40		75				1	REMOVE EXISTING GUARD RAIL. REPLACE WITH APPROACH SECTION TYPE I 75' OF NEW BEAM AND B.C.T. SEE SHEET FOR DETAILS	
MT. HOLLY TOTALS								198																	160		75				4		
																																	NOTE: FOR BRIDGE DETAILS SEE BRIDGE SHEETS 14-17