TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS: TO BE SALVAGED: REMOVE (EA.)	EXISTING SIGNS: TO BE SALVAGED: X	EXISTING SIGNS: TO BE SALVAGED: RETAIN (X)	NEW AND SALVAGED SIGNS: NEW "A" (S.F.)	NEW AND SALVAGED SIGNS: NEW "B" (S.F.)	NEW AND SALVAGED SIGNS: SALV. SIGN (EA.)	NEW AND SALVAGED SIGNS: SALV. T.I.S. (S.F.)	EXISTING POSTS: RET.	EXISTING POSTS: DRILL	EXISTING POSTS: REM.	EXISTING POSTS: SALV.	NEW SIGN POSTS: NUMBER OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL: 2.0 LB./FT.	NEW SIGN POSTS: FLANGED CHANNEL: 2.5 LB./FT.	NEW SIGN POSTS: FLANGED CHANNEL: 3.0 LB./FT.	NEW SIGN POSTS: TUBULAR ALUMINUM: 3.0" Ø	NEW SIGN POSTS: TUBULAR ALUMINUM: 3.0" □	NEW SIGN POSTS: TUBULAR ALUMINUM: 4.0" Ø	NEW SIGN POSTS: TUBULAR ALUMINUM: 4.0" Ø MOD.	NEW SIGN POSTS: W SHAPED STEEL: POST SIZE	NEW SIGN POSTS: W SHAPED STEEL: WEIGHT	NEW SIGN POSTS: W SHAPED STEEL: FTG. SIZE 24"	NEW SIGN POSTS: W SHAPED STEEL: FTG. SIZE 30"	REMARKS	FOR SIGN DETAIL SHEET: PLAN SHEET NUMBER	FOR SIGN DETAIL SHEET: STD. SHEET NUMBER
4.06 CL		24" x 30"	X			5						X		1	X													E-15B
		18" x 18"	X			2.3																						E-19B
		18" x 18"	X			2.3																						E-19B
4.11 RT	NORTH	2' x 1'	X			2						X		1	X													E-13
	103	2' x 2'	X			4																						E-13
4.13 LT	TYSON 4		X									X (2)																
	ROUND TOP MTN. SKI AREA 9		X																									
	PLYMOUTH 10		X																									
	COOLIDGE HOME 10		X																									
	NORTH		X																									
	100		X																									
	←		X																									E-23
	OKEMO MTN. SKI AREA 2	72" x 10"				5								2				X										E-23
	LUDLOW 2	72" x 10"				5																						E-23
	CHESTER 14	72" x 10"				5																						E-23
	← ROUND TOP MTN SKI AREA 9	72" x 10"				5																						E-23
	← PLYMOUTH 10	72" x 10"				5																						E-23
	← COOLIDGE HOME	72" x 10"				5																						
																											TD 529	
4.14 CL	KEEP LEFT FOR RTE. 100 NORTH	24" x 30"	X			5						X		1	X													
																												E-19B
		18" x 18"				2.3																						
4.17 RT	POSTED BRIDGE 1/2 MI. AHEAD 25 TONS 27 TONS	60" x 30"	X	X				1				X		2			X											
4.22 LT	GREEN MOUNTAIN SUGAR HOUSE 1 1/4		X	X					5			X		2			X											
	ECHO LAKE INN 5		X	X					5																			
4.23 CL					X					X																		
																												E-19B
		18" x 18"	X			2.3																						E-19B
		18" x 18"	X			2.3																						E-23
4.31 LT	JCT	2' x 1'	X			2						X		1	X													E-23
	100	2' x 2'	X			4																						
4.32 RT	STOP				X					X																		
	LEGAL LOAD LIMIT				X																							
4.36 RT	STOP				X					X																		
	LEGAL LOAD LIMIT				X																							
4.40 LT			X	X				1				X		1	X													
4.40 RT			X	X				1				X		1	X													
4.50 RT	SPEED LIMIT 50				X					X																		
4.52 LT	SPEED LIMIT 50				X					X																		
TOTALS			22			63.5		3	10							1												

FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".

PREPARED BY _____ DATE _____

CHECKED BY _____ DATE _____

LUDLOW - MT. HOLLY (SECT 1)
SHREWSBURY (SECT 2)
PROJ. NO.
STATEWIDE F-SFTY (85) S

TRAFFIC SHEET NO. [redacted] SHEET 84 OF 200

[redacted] 1986