

# 1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS.	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			RC PIPES			M.E.S.	RC PES	CONC.	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 60440	SELECTIVE THINNING	GUARD RAIL ITEMS				DELINEATORS	REMARKS
		SMALL	LARGE						D	L	TH	D	L	CL							I	II				621.80	621.20	621.60	621.50		
3.63	RT				30	4			24	8	.064																				EXTEND PIPE 8"± ADD MES AND REGRADE SLOPE SEE DETAIL "B" SHEET 4
3.69	RT				30				60	48	.138											50			40					EXTEND PIPES 16"± USE EARTH BORROW AND STONE FILL TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4	
4.10	RT				30																									USE EARTH BORROW TO COVER LEDGE OUTCROP	
4.19	RT																													REMOVE EXISTING GUIDE POSTS COST TO BE SUBSIDIARY TO OTHER ITEMS IN CONTRACT	
4.22	RT				40																									USE EARTH BORROW TO FLATTEN DRIVE SIDESLOPES SEE SHEET 5 FOR DETAILS	
4.51	RT				10	2			15	8	.064																			EXTEND PIPE 8"± FLATTEN SLOPE WITH EARTH BORROW SEE DETAIL "A" SHEET 4	
4.55	RT				10	2			15	8	.064																			EXTEND PIPE 8"± FLATTEN SLOPE WITH EARTH BORROW SEE DETAIL "A" SHEET 4	
4.63	RT				30	2	2		42	10	.109																			REMOVE TOP OF HEADER, GROUT 42" PIPE INTO EXISTING CONC. BOX. USE 10"± NEW PIPE AND MES FLATTEN SIDE SLOPE WITH EARTH BORROW SEE DETAIL "B" SHEET 4	
4.98	RT				20	2			48	8	.109																			EXTEND PIPE 8"± ADD MES USE EARTH BORROW TO FLATTEN SLOPE SEE SHEET "B" SHEET 4	
3.62	LT				10																									ADD MES TO PIPE AND FLATTEN SIDE SLOPE SEE DETAIL "B" SHEET 4	
3.68	LT				30				60	48	.138											50			40					EXTEND PIPES 16"± USE EARTH BORROW AND STONE FILL TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4	
3.72	LT				20	10		10	18	30	.064																			USE NEW PIPE AND RECONSTRUCT DRIVE SEE DETAIL "D" SHEET 4	
3.74	LT				15																									ADD END SECTIONS AND FLATTEN DRIVE SIDE SLOPES SEE DETAIL "D" SHEET 4	
4.18	LT																													REMOVE LARGE GUIDE POSTS COST SUBSIDIARY TO OTHER ITEMS IN CONTRACT	
4.62	LT				25	5	2		42	8	.109											10								REMOVE TOP OF HEADER, GROUT 42" PIPE INTO EXISTING CONC. BOX. USE 8"± NEW PIPE AND REGRADE AREA TO DRAIN SEE DETAIL "A" SHEET 4	
4.97	LT				15				48	8	.109											5								EXTEND PIPE 8"± AND FLATTEN SLOPE SEE DETAIL "A" SHEET 4	
<b>NEW HAVEN TOTALS</b>					315	27	4	10	15	16	.064											115			80						