

STATE OF VERMONT AGENCY OF TRANSPORTATION														QUANTITY SUMMARY SHEET													
SUMMARY OF ESTIMATED QUANTITIES																					DETAILED SUMMARY OF QUANTITIES						
FULL C.E. ITEMS		UTILITIES (NON-PARTICIPATING)		UTILITIES		EROSION CONTROL		LANDSCAPING		LANDSCAPING (NON-PARTICIPATING)		TRAINING		ROADWAY (NON- PARTICIPATING)		GRAND TOTAL	UNIT	DESCRIPTION	ITEM NUMBER	ROUNDING	QUANTITIES	UNIT	ITEMS				
															100	100	hour	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST							
															120	120	hour	POWER BROOM RENTAL, TYPE II	608.31	EST							
															100	100	hour	TRUCK RENTAL	608.37	EST							
															1100	1100	MGAL	DUST CONTROL WITH WATER	609.10	18.4							
															20	20	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	-							
						85										85	CY	STONE FILL, TYPE I	613.10	4.5							
						5										5	CY	STONE FILL, TYPE III	613.12	0.5							
															8150	8150	LF	VERTICAL GRANITE CURB	616.21	24.4							
															250	250	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	EST							
															15	15	LF	REMOVING AND RESETTING CURB	616.40	1.5							
															100	100	LF	REMOVAL OF EXISTING CURB	616.41	EST							
															60	60	TON	BITUMINOUS CONCRETE SIDEWALK	618.15	0.8							
															460	460	SF	DETECTABLE WARNING SURFACE	618.30	5.5							
															4	4	EACH	BOLLARDS	619.14	-							
															3	3	EACH	YIELDING MARKER POSTS	619.17	-							
															50	50	LF	CHAIN-LINK FENCE, 4 FEET	620.11	1.0							
															755	755	LF	CHAIN-LINK FENCE, 8 FEET	620.13	2.5							
															18	18	LF	GATE FOR CHAIN-LINK FENCE, 8 FEET	620.17	-							
															2	2	EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 4 FEET	620.20	-							
															7	7	EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 8 FEET	620.22	-							
															260	260	LF	REMOVAL OF EXISTING FENCE	620.55	1.0							
															1	1	EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-							
															60	60	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	2.0							
															940	940	LF	TEMPORARY TRAFFIC BARRIER	621.90	5.0							
															5600	5600	LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	37.5							
		100														100	LF	RELAYING SEWER PIPE (24")	628.30	-							
		1														1	LS	TRANSFER TO NEW SYSTEM, SANITARY SEWER	628.42	-							
															25	25	EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-							
				1												1	LS	TRANSFER TO NEW SYSTEM, WATER SYSTEM	629.42	-							
															3200	3200	HR	UNIFORMED TRAFFIC OFFICERS	630.10	21.0							
															7000	7000	HR	FLAGGERS	630.15	-							
1																1	LS	FIELD OFFICE, ENGINEERS	631.10	-							
1																1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-							
1																1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-							
9000																9000	DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-							
												1560				1560	HR	EMPLOYEE TRAINEESHIP	634.10	-							
															1	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	-							
															1	1	LS	TRAFFIC CONTROL	641.10	-							
															1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-							
															8	8	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-							
															4	4	EACH	PORTABLE ARROW BOARD	641.16	-							
															25500	25500	LF	4 INCH WHITE LINE	646.20	11.0							
															19700	19700	LF	4 INCH YELLOW LINE	646.21	40.0							
															90	90	LF	8 INCH WHITE LINE	646.22	2.0							
																		PROJECT NAME: BARRE CITY									
																		PROJECT NUMBER: FEGC F 026-1(34) C/2									
																		FILE NAME: z85b010_Quantity_Summary.xls									
																		PROJECT MANAGER: G. BAKOS									
																		DESIGNED BY: D. PECK / S. FOWLER									
																		QUANTITY SHEET #2									
																		PLOT DATE: 3/21/2011									
																		DRAWN BY: D. PECK									
																		CHECKED BY:									
																		SHEET: 13 OF 339									