



**COLD PLANING, BITUMINOUS PAVEMENT**  
SL STA 40+48 - 41+70

**SPECIAL PROVISION (DUCT BANK) (6 CONDUIT)**  
STA 122+89 - 122+92, RT-LT

**ADJUST ELEVATION OF VALVE BOX**  
STA 119+99 RT

**REMOVAL OF EXISTING FENCE**  
STA 121+81 - 122+64 RT

**SPECIAL PROVISION (ORNAMENTAL FENCE, 4 FEET)**  
STA 121+81 - 122+64 RT

**SPECIAL PROVISION (GATE FOR ORNAMENTAL FENCE, 4 FEET)**  
STA 122+10 - 122+14 RT

**SPECIAL PROVISION (REMOVE AND RESET FLAG POLE)**  
STA 119+07, RT

- NOTES:**
- SAWCUT OF EXISTING PAVEMENT & SIDEWALK SHALL BE INCIDENTAL TO ALL EXCAVATION PAY ITEMS.
  - REMOVE ABANDONED GAS LINES TO LIMITS OF FULL DEPTH CONSTRUCTION (INCIDENTAL ALL EXCAVATION PAY ITEMS). PLUG EXISTING LINES AT LIMITS OF CONSTRUCTION.
  - THE PROPOSED SEWER AND WATER UTILITIES SHOWN ON THESE GENERAL PLANS ARE FOR INFORMATIONAL PURPOSES. REFER TO THE SEWER AND WATER PLANS BY DUFRESNE GROUP FOR ACTUAL CONSTRUCTION INFORMATION.
  - SEE THE ITEM DETAIL & DRAINAGE SHEETS, DRAINAGE PROFILES, AND CROSS SECTIONS FOR PROPOSED DRAINAGE INFORMATION CORRESPONDING TO NOTE NUMBERS SHOWN BY: #
  - ALL EXISTING TELEPHONE & ELECTRIC MANHOLES SHALL BE ADJUSTED BY OTHERS.

■	PROPOSED GRANITE POST AND CHAIN FENCE	○	PROPOSED TRASH RECEPTACLE
*	PROPOSED ORNAMENTAL STREET LIGHT	⊗	PROPOSED PARKING METER POST
●	PROPOSED SIGNAL POLE WITH LUMINAIRE	⊠	PROPOSED TREE LOCATION
⊙	BORING/AUGER LOCATIONS	⊠	4' x 5' PROPOSED TREE PIT
		○	PROPOSED FIRE HYDRANT

REVISION	BY	DATE
1	DMP	5/6/2011

REVISION NO. 1: CLARIFIED LIMITS OF APPROXIMATE LOCATION OF CONTAMINATED SOILS



**VHB** Vanasse Hangen Brustlin, Inc.

PROJECT NAME:	BARRE CITY	PLOT DATE:	5/6/2011
PROJECT NUMBER:	FEGC F 026-(K34) C/2	DRAWN BY:	D. PECK
FILE NAME:	z85b010bdr_cp_C2	CHECKED BY:	
PROJECT LEADER:	G. BAKOS	SHEET	57 OF 339
DESIGNED BY:	D. PECK		
GENERAL PLAN #2			