



DELETED,
CONNECTED PIPE TO
EXISTING PIPE

COLD PLANING - BITUMINOUS PAVEMENT
 SL STA 80+48 - 81+85
 SL STA 90+48 - 90+75
 SL STA 200+48 - 200+70

- NOTES:**
- SAWCUT OF EXISTING PAVEMENT & SIDEWALK SHALL BE INCIDENTAL TO ALL EXCAVATION PAY ITEMS.
 - REMOVE ABANDONED GAS LINES TO LIMITS OF FULL DEPTH CONSTRUCTION INCIDENTAL TO ALL EXCAVATION PAY ITEMS. PLUG EXISTING LINES AT LIMITS OF CONSTRUCTION.
 - THE PROPOSED SEWER AND WATER UTILITIES SHOWN ON THESE GENERAL PLANS ARE FOR INFORMATIONAL PURPOSES. REFER TO THE SEWER AND WATER PLANS BY DUFRESNE GROUP FOR ACTUAL CONSTRUCTION INFORMATION.
 - SEE THE ITEM DETAIL & DRAINAGE SHEETS, DRAINAGE PROFILES, AND CROSS SECTIONS FOR PROPOSED DRAINAGE INFORMATION CORRESPONDING TO NOTE NUMBERS SHOWN BY: #
 - ALL EXISTING TELEPHONE & ELECTRIC MANHOLES SHALL BE ADJUSTED BY OTHERS.

■	PROPOSED GRANITE POST AND CHAIN FENCE	○	PROPOSED TRASH RECEPTACLE
*	PROPOSED ORNAMENTAL STREET LIGHT	⊗	PROPOSED PARKING METER POST
●	PROPOSED SIGNAL POLE WITH LUMINAIRE	⊠	PROPOSED TREE LOCATION
⊙	BORING/AUGER LOCATIONS	⊞	4' x 5' PROPOSED TREE PIT
		⊕	PROPOSED FIRE HYDRANT



VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME:	BARRE CITY	PLOT DATE:	3/9/2011
PROJECT NUMBER:	FEGC F 026-(134) C/2	DRAWN BY:	D. PECK
FILE NAME:	z85b010bdr_cp_C2	CHECKED BY:	
PROJECT LEADER:	G. BAKOS	SHEET	59 OF 339
DESIGNED BY:	D. PECK		
GENERAL PLAN #4			