



CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS
 SL STA 10+50 - 12+61 RT
 SL STA 12+83 - 12+91 LT
 SL STA 12+97 - 15+66 RT

REMOVAL AND DISPOSAL OF GUARDRAIL
 SL STA 13+04 - 13+80 RT

MANUFACTURED TERMINAL SECTION, FLARED
 SL STA 13+31 - 13+80 RT

REMOVAL OF EXISTING FENCE
 SL STA 12+25 - 12+58 RT
 SL STA 13+24 - 15+21 RT

CHAIN-LINK FENCE, 8 FEET
 SL STA 12+95 - 15+80 RT (VINYL COATED, PAINTED BLACK)

GATE FOR CHAIN-LINK FENCE, 8 FEET
 SL STA 13+28 RT (18') (VINYL COATED, PAINTED BLACK)

CHAIN-LINK FENCE, 4 FEET
 SL STA 12+25 - 12+44, RT

COLD PLANING, BITUMINOUS PAVEMENT
 SL STA 11+75 - 12+66

STONE FILL, TYPE III
 SL STA 14+57 RT
 SL STA 15+28 RT
 SL STA 15+59 RT

CONSTRUCT DRIVE
 SL STA 13+11 RT (W/ 3" CURB REVEAL) (SEE SHEET #6)

- NOTES:**
- ALL 8-FOOT HIGH CHAIN-LINK FENCE AND GATES FOR CHAIN-LINK FENCE, INCLUDING ASSOCIATED HARDWARE AND FURNISHINGS SHALL BE VINYL COATED, COLOR BLACK.
 - SEE THE ITEM DETAIL & DRAINAGE SHEETS, DRAINAGE PROFILES, AND CROSS SECTIONS FOR PROPOSED DRAINAGE INFORMATION CORRESPONDING TO NOTE NUMBERS SHOWN BY: #
 - SEE TRAFFIC SIGNAL PLANS FOR CONDUIT AND PULL BOX INFORMATION (SHEET 165).
 - ALL EXISTING TELEPHONE & ELECTRIC MANHOLES SHALL BE ADJUSTED BY OTHERS.

■	PROPOSED GRANITE POST AND CHAIN FENCE	○	PROPOSED TRASH RECEPTACLE
*	PROPOSED ORNAMENTAL STREET LIGHT	⊗	PROPOSED PARKING METER POST
●	PROPOSED SIGNAL POLE WITH LUMINAIRE	⊠	4' x 5' PROPOSED TREE PIT
⊙	BORING/AUGER LOCATIONS	⊕	PROPOSED FIRE HYDRANT

20 0 20 40
 FEET

VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME:	BARRE CITY	PLOT DATE:	3/9/2011
PROJECT NUMBER:	FEGC F 026-(134) C/2	DRAWN BY:	D. PECK
FILE NAME:	z85b010bdr_cp_C2	CHECKED BY:	
PROJECT LEADER:	G. BAKOS	SHEET	63 OF 339
DESIGNED BY:	D. PECK		
GENERAL PLAN #8			