



**DECIDUOUS TREES**  
 STA 123+58 LT  
 STA 124+12 RT  
 STA 124+05 LT  
 STA 124+63 RT  
 STA 124+79 LT  
 STA 125+35 LT  
 STA 125+75 RT  
 STA 126+64 RT  
 STA 127+75 RT  
 STA 127+60 LT  
 STA 128+22 RT  
 STA 128+40 LT  
 STA 128+88 RT  
 STA 129+50 RT

**SPECIAL PROVISION (STEEL BENCH WITHOUT BACK)**  
 STA 126+10 RT

**SPECIAL PROVISION (STEEL BENCH WITH BACK)**  
 STA 126+80 LT

**SPECIAL PROVISION (TRASH RECEPTACLE)**  
 STA 123+77 RT  
 STA 125+39 LT  
 STA 126+69 RT  
 STA 126+78 LT  
 STA 128+09 RT  
 STA 129+23 LT

**SPECIAL PROVISION (GRANITE POST AND CHAIN FENCE)**  
 STA 124+22 - 124+81 RT  
 STA 125+61 - 125+79 LT  
 STA 126+69 - 126+87 LT  
 STA 129+59 - 129+75 LT

**SPECIAL PROVISION (BICYCLE RACK)**  
 STA 123+34 RT  
 STA 126+75 RT  
 STA 128+66 LT  
 STA 129+24 RT

**REMOVING MEDIUM TREES**  
 STA 124+79 RT  
 STA 125+18 LT  
 STA 128+01 RT

**TREE PROTECTION ZONE/TPZ**  
 STA 125+28 - 125+35 RT  
 STA 125+41 - 126+17 RT  
 STA 126+04 - 126+37 LT  
 STA 126+17 - 126+23 RT  
 STA 126+90 LT - SL STA 61+11 LT

**LEGEND:**

- EXISTING MEDIUM OR LARGE TREE OR STUMP TO BE REMOVED
- PROPOSED DECIDUOUS TREE (OUTSIDE OF SIDEWALK)
- PROPOSED DECIDUOUS TREE WITH 4' x 5' TREE PIT
- PROPOSED SHRUB
- COBBLESTONE PAVERS
- IMPRINTED 5" CONCRETE SIDEWALK
- CU STRUCTURAL SOIL
- PROPOSED GRANITE POST AND CHAIN FENCE
- PROPOSED ORNAMENTAL STREET LIGHT
- TREE PROTECTION ZONE / TPZ
- PROPOSED SIGNAL POLE WITH LUMINAIRE
- PROPOSED STEEL BENCH WITH BACK
- PROPOSED STEEL BENCH WITHOUT BACK
- PROPOSED PARKING METER POST
- PROPOSED TRASH RECEPTACLE
- PROPOSED BICYCLE RACK

**SPECIAL PROVISION (CU STRUCTURAL SOIL)**  
 STA 123+43 - 124+20 LT  
 STA 123+97 - 124+83 RT  
 STA 124+64 - 124+94 LT  
 STA 125+20 - 125+50 LT  
 STA 125+60 - 125+90 RT  
 STA 126+49 - 126+79 RT  
 STA 127+60 - 128+37 RT  
 STA 127+45 - 127+75 LT  
 STA 128+25 - 128+55 LT  
 STA 128+73 - 129+03 RT  
 STA 129+35 - 129+65 RT

**REMOVING LARGE TREE**  
 STA 126+95 RT

**NOTES:**

1. ALL MUNICIPAL GRANITE BENCHES SHALL BE REMOVED AND RESET BY THE CITY.
2. ALL TREE PROTECTION ZONES SHALL BE PAID AS A LUMP SUM UNDER ITEM 656.85 - TREE PROTECTION.
3. ALL TREES AND NAMED CULTIVARS HAVE BEEN CHECKED AND ALL PATENTS HAVE EXPIRED EXCEPT AS NOTED BELOW \*\*.

SYMBOL	COMMON NAME	BOTANICAL NAME	QTY.	UNIT	SIZE	SPACING / COMMENTS
UAC	ACCOLADE ELM	ULMUS CARPINIFOLIA ACCOLADE	2	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
ARA	ARMSTRONG RED MAPLE	ACER RUBRUM "ARMSTRONG"	5	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
AFAB	AUTUMN BLAZE MAPLE	ACER FREMANII X AUTUMN BLAZE	2	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
QRP	REGAL PRINCE COLUMNAR OAK	QUERCUS RxB, LONG**	4	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
GTS	SHADEMASTER HONEYLOCUST	GLEDDITSIA TRIACANTHOS INERMIS	1	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.

\*\* ALL TREES SHALL BE PLANTED IN THE SPRING

- \*\* ALTERNATIVES FOR REGAL PRINCE COLUMNAR OAK ARE AS FOLLOWS:
1. CRIMSON SPIRE OAK (QUERCUS ROBUR X Q. ALBA "CRIMSCHMIDT")
  2. BOWHALL MAPLE (ACER RUBRUM "BOWHALL")
  3. KARPICK MAPLE (ACER RUBRUM "KARPICK")



**VHB** Vanasse Hangen Brustlin, Inc.

PROJECT NAME: BARRE CITY  
 PROJECT NUMBER: FECC F 026-(134) C/2  
 FILE NAME: z85b010bdr\_ld\_c2  
 PROJECT LEADER: G. BAKOS  
 DESIGNED BY: D. PECK  
 LANDSCAPING PLAN #3

PLOT DATE: 3/23/2011  
 DRAWN BY: D. PECK  
 CHECKED BY:  
 SHEET 87 OF 339