



**SPECIAL PROVISION (GRANITE POST AND CHAIN FENCE)**  
 STA 129+75 - 130+01 LT

**SPECIAL PROVISION (TRASH RECEPTACLE)**  
 STA 129+90 RT  
 STA 130+98 RT  
 STA 131+99 LT  
 STA 132+55 RT  
 STA 135+41 RT  
 STA 135+42 LT

**SPECIAL PROVISION (STEEL BENCH WITHOUT BACK)**  
 STA 133+92 LT  
 STA 134+70 LT

**SPECIAL PROVISION (STEEL BENCH WITH BACK)**  
 STA 130+65 LT  
 STA 131+89 LT  
 STA 131+97 LT

**DECIDUOUS TREES**  
 STA 130+13 LT  
 STA 131+35 LT  
 STA 131+35 RT  
 STA 132+00 RT  
 STA 132+00 LT  
 STA 132+60 RT  
 STA 133+21 LT  
 STA 133+21 RT  
 STA 133+85 LT  
 STA 133+87 RT  
 STA 134+45 LT  
 STA 134+45 RT  
 STA 135+07 RT  
 STA 135+70 LT  
 STA 135+70 RT

**SPECIAL PROVISION (CU STRUCTURAL SOIL)**  
 STA 129+98 - 130+28 LT  
 STA 131+20 - 131+50 LT  
 STA 131+20 - 131+50 RT  
 STA 131+85 - 131+15 LT  
 STA 131+85 - 131+15 RT  
 STA 132+45 - 132+75 RT  
 STA 133+06 - 133+36 LT  
 STA 133+06 - 133+36 RT  
 STA 133+70 - 134+00 LT  
 STA 133+72 - 134+02 RT  
 STA 134+30 - 134+60 LT  
 STA 134+30 - 134+60 RT  
 STA 134+92 - 135+22 RT  
 STA 135+55 - 135+85 LT  
 STA 135+55 - 135+85 RT

**REMOVING MEDIUM TREES**  
 STA 131+39 LT  
 STA 131+83 LT  
 STA 132+31 LT  
 STA 134+15 LT  
 STA 134+75 LT

SYMBOL	COMMON NAME	BOTANICAL NAME	QTY.	UNIT	SIZE	SPACING / COMMENTS
QRP	REGAL PRINCE COLUMNAR OAK	QUERCUS RxB. LONG **	4	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
UVF	VALLEY FORGE AMERICAN ELM	ULMUS AMERICAN "VALLEY FORGE"	4	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
GTS	SHADEMASTER HONEYLOCUST	GLEDITSIA TRIACANTHOS INERMIS	3	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.
ARA	ARMSTRONG RED MAPLE	ACER RUBRUM "ARMSTRONG"	4	B&B	2"-2½" CAL	5' TO 6' MIN. BRANCH HT.

\* ALL TREES SHALL BE PLANTED IN THE SPRING

**LEGEND:**

	EXISTING MEDIUM OR LARGE TREE OR STUMP TO BE REMOVED		PROPOSED GRANITE POST AND CHAIN FENCE
	PROPOSED DECIDUOUS TREE (OUTSIDE OF SIDEWALK)		PROPOSED ORNAMENTAL STREET LIGHT
	PROPOSED DECIDUOUS TREE WITH 4' x 5' TREE PIT		TREE PROTECTION ZONE / TPZ
	PROPOSED SHRUB		PROPOSED SIGNAL POLE WITH LUMINAIRE
	COBBLESTONE PAVERS		PROPOSED STEEL BENCH WITH BACK
	IMPRINTED 5" CONCRETE SIDEWALK		PROPOSED STEEL BENCH WITHOUT BACK
	CU STRUCTURAL SOIL		PROPOSED PARKING METER POST
			PROPOSED TRASH RECEPTACLE
			PROPOSED BICYCLE RACK

- NOTES:**
- ALL MUNICIPAL GRANITE BENCHES SHALL BE REMOVED AND RESET BY THE CITY.
  - ALL TREE PROTECTION ZONES SHALL BE PAID AS A LUMP SUM UNDER ITEM 656.85 - TREE PROTECTION.
  - ALL TREES AND NAMED CULTIVARS HAVE BEEN CHECKED AND ALL PATENTS HAVE EXPIRED EXCEPT AS NOTED BELOW \*\*.

- \*\* ALTERNATIVES FOR REGAL PRINCE COLUMNAR OAK ARE AS FOLLOWS:
- CRIMSON SPIRE OAK (QUERCUS ROBUR X Q. ALBA "CRIMSCHMIDT")
  - BOWHALL MAPLE (ACER RUBRUM "BOWHALL")
  - KARPICK MAPLE (ACER RUBRUM "KARPICK")



**VHB** Vanasse Hangen Brustlin, Inc.

PROJECT NAME: BARRE CITY	PLOT DATE: 3/9/2011
PROJECT NUMBER: FECC F 026-1(34) C/2	DRAWN BY: D. PECK
FILE NAME: z85b010bdr_id_C2	CHECKED BY:
PROJECT LEADER: G. BAKOS	LANDSCAPING PLAN #4
DESIGNED BY: D. PECK	SHEET 88 OF 339