STATE OF VERMONT
AGENCY OF TRANSPORTATION

TEMPORARY TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) LB/FT 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (IN) FOUND-ATION	LB/FT 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
SUMMER STREET																																			
420+79, RT	DO NOT BLOCK INTERSECTION	1	24	30	5.00						1					X			X														TEMPORARY SIGN R10-7		
421+95, LT	NO PARKING ANY TIME	1	12	18	1.50						1					X			X														TEMPORARY SIGN R7-1		
ELM STREET																																			
703+84, RT	ONLY NO PARKING ANY TIME	1 1	36 12	30 18	7.50 1.50						1						X																VR-922 TEMPORARY SIGNS R7-1		E-145A
704+76, RT	LEFT LANE MUST TURN LEFT NO PARKING ANY TIME	1 1	30 12	30 18	6.25 1.50						1						X																R3-7L TEMPORARY SIGNS R7-1		
705+77, RT	NO PARKING ANY TIME	1	12	18	1.50						1					X			X														TEMPORARY SIGN R7-1		
706+69, RT	NO PARKING ANY TIME	1	12	18	1.50						1					X			X														TEMPORARY SIGN R7-1		
												FT	FT	FT	FT	FT 60	FT 30		EA	LB	LB	LB		LB	LB	LB	LB								
SUB TOTALS					SF 26.25	SF	EA.	SF				FT			FT 90				EA 4	LB			EA.	LB			EA.	EA.	LB						
FROM SHEET 202					34.25										156				10																
TOTALS					60.50										246				14																

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

AVERAGE POST LENGTH = 15 FT

NOTE:

PAYMENT FOR TEMPORARY TRAFFIC SIGNS WILL BE INCLUDED IN THE UNIT PRICE BID FOR CONTRACT ITEM 641.10.

VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME: BARRE CITY
PROJECT NUMBER: FEGC F 026-1(34) C/2

FILE NAME: z85b010_TTSSS.dgn PLOT DATE:
PROJECT LEADER: G. BAKOS DRAWN BY: DMP / JAR
DESIGNED BY: DMP / MDS CHECKED BY:
TEMPORARY TRAFFIC SIGN SUMMARY SHEET SHEET 203 OF 339