



SPECIAL PROVISION (CU STRUCTURAL SOIL)
 STA 116+90 - 117+40 LT
 STA 117+62 - 118+02 LT
 STA 117+80 - 118+20 RT
 STA 118+22 - 118+62 LT
 STA 118+82 - 119+22 LT
 STA 119+42 - 119+82 LT
 STA 120+75 - 121+15 LT
 STA 121+37 - 121+77 LT
 STA 121+66 - 122+06 RT
 STA 122+19 - 122+59 RT
 STA 122+83 - 123+17 RT

LANDSCAPE BACKILL, TRUCK MEASUREMENT
 STA 116+90 - 120+08 LT
 STA 120+44 - SL 40+56 LT
 STA 120+70 - 121+73 RT (ISLAND)

SPECIAL PROVISION (BICYCLE RACK)
 STA 122+65 LT

SPECIAL PROVISION (TRASH RECEPTACLE)
 STA 118+19 LT
 STA 121+82 RT
 STA 122+49 LT

SPECIAL PROVISION (GRANITE POST AND CHAIN FENCE)

STA 116+90 - 117+14 LT
 STA 117+27 - 117+47 LT
 STA 117+57 - 117+75 LT
 STA 117+89 - 118+07 LT
 STA 118+17 - 118+35 LT
 STA 118+49 - 118+67 LT
 STA 118+77 - 118+95 LT
 STA 119+09 - 119+27 LT
 STA 119+37 - 119+55 LT
 STA 119+69 - 119+87 LT
 STA 119+96 - 120+05 LT
 STA 120+48 - 120+58 LT
 STA 120+69 - 120+87 LT
 STA 121+03 - 121+22 LT
 STA 121+32 - 121+50 LT
 STA 121+64 - 121+82 LT
 STA 121+94 - 122+38 LT

RETAIN BARRE AUDITORIUM SIGN
 GRANITE BORDER TO BE REMOVED BY CITY
 EXISTING BENCH (BY CITY)

REMOVE & STOCKPILE EXISTING PLANTING BED MATERIAL. REPLACE IN PLANTING BED AFTER NEW CURB & SIDEWALK HAVE BEEN INSTALLED.

LEGEND:

	EXISTING MEDIUM OR LARGE TREE OR STUMP TO BE REMOVED		PROPOSED GRANITE POST AND CHAIN FENCE
	PROPOSED DECIDUOUS TREE (OUTSIDE OF SIDEWALK)		PROPOSED ORNAMENTAL STREET LIGHT
	PROPOSED DECIDUOUS TREE WITH 4' x 5' TREE PIT		TREE PROTECTION ZONE / TPZ
	PROPOSED SHRUB		PROPOSED STEEL BENCH WITH BACK
	COBBLESTONE PAVERS		PROPOSED STEEL BENCH WITHOUT BACK
	IMPRINTED 5" CONCRETE SIDEWALK		PROPOSED PARKING METER POST
	CU STRUCTURAL SOIL		PROPOSED TRASH RECEPTACLE
			PROPOSED BICYCLE RACK

DECIDUOUS TREES

STA 116+93 LT
 STA 117+21 LT
 STA 117+82 LT
 STA 118+00 RT
 STA 118+34 RT
 STA 118+42 LT
 STA 119+02 LT
 STA 119+62 LT
 STA 120+95 LT
 STA 121+57 LT
 STA 121+86 RT
 STA 122+39 RT
 STA 122+97 RT

EVERGREEN SHRUBS

STA 116+91 - 120+07 LT
 STA 120+47 - 122+56 LT
 STA 119+00 - 120+00 RT

TREE PROTECTION ZONE/TPZ

STA 116+90 - 117+24 RT
 STA 118+89 - 119+57 RT
 STA 119+71 - 120+12 RT
 SL STA 40+68 RT - STA 123+25 LT
 STA 119+89 - 120+12 RT

REMOVING MEDIUM STUMPS

STA 122+19 RT
 REMOVING MEDIUM TREES
 STA 121+73 RT

SPECIAL PROVISION (CEDAR BARK MULCH)

SYMBOL	COMMON NAME	BOTANICAL NAME	QTY.	UNIT	SIZE	SPACING / COMMENTS
GTS	SHADEMASTER HONEYLOCUST	GLEDITSIA TRIACANTHOS INERMIS	7	B&B	2"-2 1/2" CAL	5' TO 6' MIN. BRANCH HT.
UNH	NEW HARMONY AMERICAN ELM	ULMUS AMERICANA NEW HARMONY	3	B&B	2"-2 1/2" CAL	5' TO 6' MIN. BRANCH HT.
JSG	SEAGREEN JUNIPER	JUNIPERUS CHINENSIS SEA GREEN	286	2 GAL.	24"-30" HT.	SPRING PLANTING
OR	NORTHERN RED OAK	QUERCUS RUBRA	2	B&B	2"-2 1/2" CAL	5' TO 6' MIN. BRANCH HT.
AFAB	AUTUMN BLAZE MAPLE	ACER FREMANII X AUTUMN BLAZE	1	B&B	2"-2 1/2" CAL	5' TO 6' MIN. BRANCH HT.

• ALL TREES SHALL BE PLANTED IN THE SPRING

- NOTES:**
- ALL MUNICIPAL GRANITE BENCHES SHALL BE REMOVED AND RESET BY THE CITY.
 - ALL TREE PROTECTION ZONES SHALL BE PAID AS A LUMP SUM UNDER ITEM 656.85 - TREE PROTECTION.
 - ALL TREES AND NAMED CULTIVARS HAVE BEEN CHECKED AND ALL PATENTS HAVE EXPIRED.



VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME: BARRE CITY
 PROJECT NUMBER: FECC F 026-(134) C/2
 FILE NAME: z85b010bdr_ld_C2
 PROJECT LEADER: G. BAKOS
 DESIGNED BY: D. PECK
 LANDSCAPING PLAN #2
 PLOT DATE: 3/9/2011
 DRAWN BY: D. PECK
 CHECKED BY:
 SHEET 86 OF 339