STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILE MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (IN)	HEIGHT (IN)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL LB/FT 1.12	2.0	3.0	SQUARE STEEL (IN) LB/FT 1.88	1.75	2.0	2.42	2.5	3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) LB/FT 1.3	3.0	4.0	1.7	4.0 MOD	1.7	FOUND-ATION	TUBULAR STEEL Ø (IN) LB/FT 7.6	3.0	9.0	3.5	10.8	4.0	14.6	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																																					
SUMMER STREET																																																
408+72, RT	B-B GMTA CHURCH PARKING USE WEST ST	1	* 36	* 36	3.18	2					1								X			X																					* SIZE = 36" x 36" x 36"	SHS R1-2		
		1	30	30	6.25														14.75'																									SHS R3-2		
409+16, LT		1	30	30	6.25						1						X					X																					FYG	SHS W11-2		
		1	24	12	2.00												15.0'																										FYG	SHS W16-7pL		
410+36, LT	SPEED LIMIT 25	1	24	30	5.00						1						X					X																							SHS R2-1		
																	13.33'																													
411+62, LT	SAL. NO PARKING ANYTIME	1	30	30	6.25	1					1						X					X																					NO PARKING SIGN FACES CURB-90 TO PED. SIGN. SALVAGED DOWN ARROW.	FYG	SHS W11-2	
		+	~~24~~	~~12~~	~~2.00~~												15.0'																										FYG	SHS W16-7pL		
411+66, LT	West ⇒ STOP CHURCH PARKING	1	24	12	2.00	1					1								X			X																							SHS D3-1		
		1	36	36	9.00														15.33'																									SHS R1-1		
411+67, RT		1	30	30	6.25				+		1						X																											REPLACE PRIMARY SIGN; ~~RETAIN~~ SUPPLEMENTAL SIGN AND POST ADD NEW	SHS W11-2		
		1	24	12	2.00		1										15.75'																											FYG		
411+70, RT	B-B ONE WAY ONE WAY DO NOT ENTER	1	36	12	3.00						1								X			X																					SET R6-1R & R6-1L BAK TO BACK WITH R5-1 FACING SUMMER ST	SHS R6-1L		
		1	36	12	3.00																																							SHS R6-1R		
		1	36	36	9.00														14.83'																									SHS R5-1		
412+08, RT	STOP	1	36	36	9.00						1								X			X																							SHS R1-1		
																			13.75'																											
412+95, LT	SCHOOL	1	36	36	6.75						1						X					X																						FYG	SHS S1-1		
		1	24	8	1.33												14.0'																										FYG	SHS S4-3		
												FT	FT	FT	FT	FT	~~60~~ 73.08	FT ~~60~~ 58.66		EA 8		LB	LB	LB			LB	LB	LB	LB											
SUB TOTALS					SF 80.26	SF	EA. ~~1~~ 4	SF				FT			FT				~~120~~ 151.74			LB				EA.		LB							EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

AVERAGE POST LENGTH = 15 FT

BOW = BLACK LEGEND ON WHITE BACKGROUND - PLAQUE
GOW = GREEN LEGEND ON WHITE BACKGROUND - PLAQUE
WOB = WHITE LEGEND ON BLUE BACKGROUND - PLAQUE
FYG = BLACK LEGEND ON FLUORESCENT YELLOW-GREEN BACKGROUND
SHS = FHWA STANDARD HIGHWAY SIGNS BOOK

VHB Vanasse Hangen Brustlin, Inc.

PROJECT NAME: BARRE CITY
PROJECT NUMBER: FEGC F 026-1(34) C/2

FILE NAME: 85b010_TSSS_C2
PROJECT LEADER: G. BAKOS
DESIGNED BY: MDS
TRAFFIC SIGN SUMMARY SHEET

PLOT DATE: 3/31/2011
DRAWN BY: CMD
CHECKED BY:
SHEET 128 OF 339