

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL			RC PIPES			MES	RC PES	CONC	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 604.40	SELECTIVE THINNING	GUARD RAIL ITEMS						DELINEATORS	REMARKS		
		D	L						TH	D	L	CL	I	II							621.80	621.21				621.20	621.70	621.60	621.50						
3.49-3.50	RT							50																	71		25	1		1				REMOVE EXISTING RAIL. CONNECT GUARD RAIL APPROACH SECTION, TYPE I TO HEAVY DUTY BEAM ON BRIDGE. SEE SHEETS 3 AND 30 FOR DETAILS.	
3.50-3.51	RT																										25						SEE SHEET 30 FOR DETAILS.		
3.51-3.52	RT							3																	38		25	1	1				REMOVE EXISTING RAIL. CONNECT GUARD RAIL APPROACH SECTION, TYPE I TO THE HEAVY DUTY BEAM ON THE BRIDGE. WRAP NLY END AROUND DRIVE. SEE SHEETS 3 AND 30 FOR DETAILS.		
3.48-3.49	LT							50																	71		25	1		1				REMOVE EXISTING RAIL. CONNECT GUARD RAIL APPROACH SECTION, TYPE I MOD. TO THE HEAVY DUTY BEAM ON THE BRIDGE. SEE SHEETS 3 AND 30 FOR DETAILS.	
3.49-3.50	LT																										25						SEE SHEET 30 FOR DETAILS.		
3.50-3.51	LT							49																	40			1		1				REMOVE EXISTING GUARD RAIL. CONNECT GUARD RAIL APPROACH SECTION, TYPE I MOD. TO THE HEAVY DUTY BEAM ON THE BRIDGE. SEE SHEETS 3 AND 30 FOR DETAILS.	
3.94-3.95	RT							5																	106		75	1		1				REMOVE EXISTING RAIL. CONNECT 621.70 MOD. TO HEAVY DUTY BEAM ON BRIDGE. WRAP SLY END OF STEEL BEAM AROUND PULLOUT. SEE SHEETS 3 AND 31 FOR DETAILS.	
3.95-3.96	RT																										87.5						SEE SHEET 31 FOR DETAILS.		
3.98-3.99	RT							3																	50		25	1	1				REMOVE EXISTING RAIL. CONNECT 621.70 MOD. TO HEAVY DUTY BEAM ON BRIDGE. WRAP NLY END AROUND DRIVE. SEE SHEETS 3 AND 31 FOR DETAILS.		
3.94-3.95	LT							50																	65		25	1		1				REMOVE EXISTING RAIL. CONNECT 621.70 MOD. TO HEAVY DUTY BEAM ON BRIDGE. SEE SHEETS 3 AND 31 FOR DETAILS.	
3.96-3.97	LT																										87.5						SEE SHEET 31 FOR DETAILS.		
3.98-3.99	LT							50																	75		25	1		1				REMOVE EXISTING RAIL. CONNECT 621.70 MOD. TO HEAVY DUTY BEAM ON BRIDGE. SEE SHEETS 3 AND 31 FOR DETAILS.	
WORCESTER TOTALS								260																		516	225	225	8	3	5				