

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			RC PIPES			M.E.S.	RCPE	CONC.	STEEL	REBAR DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 60440	SELECTIVE THINNING	GUARD RAIL ITEMS				REMARKS
		SMALL	LARGE						D	L	TH	D	L	CL							I	II				62180	62120	62160	62150	
WEATHERSFIELD																														
6.38	LT				15	2					18	12	III		1-18														REMOVE HEADWALL. ADD 8"± NEW PIPE AND ROPES. USE EARTH BORROW TO FLATTEN SLOPE. SEE DETAIL "H" SHEET 4	
6.45	LT																	1										RECONSTRUCT D.I.		
6.53	LT																	1										RECONSTRUCT D.I.		
6.72	LT																	1										RECONSTRUCT D.I.		
WINDSOR																														
0.24	LT				25	2	2				24	4	III			2.0	200		1									REMOVE HEADWALL ADD 4"± NEW PIPE CONSTRUCT D.I. SEE DETAIL "E" SHEET 4		
0.56	LT																	1										RECONSTRUCT DI		
0.60-0.62	LT							100																	125	150	2	REPLACE EXISTING GUARD RAIL SEE SHEET 3 FOR DETAILS		
0.67	LT																	1										RECONSTRUCT DI		
0.76	LT																	1										RECONSTRUCT DI		
0.85	LT				30	6	4		52X77	16	.109															15		REMOVE HEADWALL EXTEND PIPE FLATTEN SLOPE SEE DETAIL "A" SHEET 4		
0.91	LT				30	15			18	22	.064					3.0	300		2	20								CONNECT PIPES W/ 4'X6' DI W/2 GRATES		
0.99	LT				10	8	2									2.0	200		1									REMOVE HEADWALL CONSTRUCT DI REGRADE DITCH SEE DETAIL "E" SHEET 4		
SHEET TOTAL																														
					130	25	10	100	18	22	.064	18	12	III	1-18	7.0	700	6	4	35					125	150	2			
									52X77	16	.109	24	4	III																
TOTAL FROM SHEET																														
					30	6	397					15	36	III											2305	3975	1	5		
PROJECT TOTAL																														
					160	25	16	497	18	22	.064	15	36	III	1-18	7.0	700	6	4	35					2430	4125	1	7		
									52X77	16	.109	18	12	III																
												24	4	III																