

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS	NORTHBOUND		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			RC PIPES			M.E.S.	RC.P.E.S.	CONC.	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 60440	SELECTIVE THINNING	GUARD RAIL ITEMS				REMARKS		
		SMALL	LARGE						D	L	TH	D	L	CL							I	II				62180	62120	62160	62150		DELINEATORS	
WEATHERSFIELD																																
6.33-6.38	RT							121																		420		725		2	PAY REMOVAL OF GUIDE POSTS AS REMOVAL AND DISPOSAL OF GUARD RAIL BEGIN NEW GUARD RAIL 300' +/- SOUTHERLY SEE SHEET 3 FOR DETAILS	
6.36	RT				10		2					15	12	III																	REMOVE HEADWALL, EXTEND PIPE 8'± USE EARTH BORROW TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4	
6.52	RT				10		2					15	12	III																	REMOVE HEADWALL EXTEND PIPE 8'± USE EARTH BORROW TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4	
6.64	RT																														CUT OFF POLE STUB COST SUBSIDIARY TO OTHER ITEMS	
6.73	RT				10		2					15	12	III																	REMOVE HEADWALL EXTEND PIPE 8'± USE EARTH BORROW TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4	
WINDSOR																																
0.23-0.85	RT							169																				3250		1	1	WRAP NEW GUARD RAIL AROUND DRIVE TO SEWER PLANT AT 0.85 +/- SEE SHEET 3 FOR DETAILS
0.52-0.71	RT																									775						PAY REMOVAL OF GUIDE POSTS AS REMOVAL AND DISPOSAL OF EXISTING GUARD RAIL
0.71-0.85	RT																									760						REMOVE EXISTING GUARD RAIL
0.91-0.98	RT							107																				350		2		NEW SECTION OF GUARD RAIL SEE SHEET 3 FOR DETAILS
SHEET TOTAL					30		6	397				15	36	III												1965		4325		1	5	