1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS.	REMOVING TREES SMALL	REMOVING TREES LARGE	UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE D	METAL PIPE L	METAL PIPE TH	RCP PIPES D	RCP PIPES L	RCP PIPES CL	M.E.S	R.C.P.E.S.	CONC.	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL I	STONE FILL II	TIMBER CURB	ITEM 604.40	SELECTIVE THINNING		GUARD RAIL ITEMS 621.15	621.20	621.70	621.60	621.50	DELINEATORS	REMARKS
3.94	RT.			10	10			5																			32	112.5	1		2		CONNECT GUARD RAIL APPROACH SECTION, TYPE I MOD. TO H.D. BEAM ON BRIDGE. CONNECT 112.5FT. OF NEW STEEL BEAM TO APPROACH SECTION. INSTALL BCT.
3.94	LT.																											12.5		2			CONNECT GUARD RAIL APPROACH SECTION TYPE I MOD. TO H.D. BEAM ON BRIDGE. CONNECT 12.5FT. OF NEW STEEL BEAM TO APPROACH SECTION. INSTALL BCT.
																													1				
JOHNSON TOTALS				10	10			5																			32	125	2	2	2		

JOHNSON
1985 STATEWIDE SAFETY PROJECT
SHEET 47 OF [illegible]