1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS.	REMOVING TREES SMALL	REMOVING TREES LARGE	UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE D	METAL PIPE L	METAL PIPE TH	RC PIPES D	RC PIPES L	RC PIPES CL	M.E.S	R.C.P.E.S.	CONC	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL I	STONE FILL II	TIMBER CURB	ITEM 604.40	SELECTIVE THINNING	GUARD RAIL ITEMS 621.80			621.20		621.60	621.50	DELINEATORS	REMARKS
MT. HOLLY																																			
1.04	RT							49																		40						1			REMOVE EXISTING GUARD RAIL, REPLACE WITH APPROACH SECTION TYPE I AND B.C.T. SEE SHEET 3 FOR DETAILS.
1.07	RT							49																		40						1			REMOVE EXISTING GUARD RAIL, REPLACE WITH APPROACH SECTION TYPE I AND B.C.T. SEE SHEET 3. FOR DETAILS.
1.04	LT							49																		40						1			REMOVE EXISTING GUARD RAIL, REPLACE WITH APPROACH SECTION TPYE I AND B.C.T. SEE SHEET 3 FOR DETAILS.
1.07	LT							51																		40			75			1			REMOVE EXISTING GUARD RAIL, REPLACE WITH APPROACH SECTION TYPE I 75' OF NEW BEAM AND B.C.T. SEE SHEET FOR DETAILS
MT. HOLLY TOTALS								198																		160			75			4			

NOTE: FOR BRIDGE DETAILS SEE BRIDGE SHEETS 14–17

LUDLOW–MT. HOLLY–SHREWSBURY
1985 STATEWIDE SAFETY PROJECT
SHEET 61 OF 200 SHEETS