

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS		NEW AND SALVAGED SIGNS				EXISTING POSTS				NEW SIGN POSTS								REMARKS	FOR SIGN DETAIL SHEET						
			TO BE SALVAGED REMOVE (EA.)	RETAIN (X)	NEW "A" (S.F.)	NEW "B" (S.F.)	SALV. SIGN (EA.)	SALV. T.J.S.(S.F.)	RET.	DRILL	REM.	SALV.	NUMBER OF POSTS	FLANGED CHANNEL			TUBULAR ALUMINUM					W SHAPED STEEL		PLAN SHEET NUMBER	STD. SHEET NUMBER			
														2.0 LB./FT.	2.5 LB./FT.	3.0 LB./FT.	3.0" Ø	3.0" □	4.0" Ø	4.0" MOD.		POST SIZE	WEIGHT			PTG. SIZE		
0.21 LT.	PROHIB	3' x 3'			9							2				X												E-15B
	TURN SIGNAL REQ.	3' x 3'			9																							E-15B
0.22 RT	SPEED LIMIT 50 EXIST. / SPEED LIMIT 55 NEW	3' x 4'	X		12							1				X												E-15B
0.23 LT	TO EXIST. / JCT NEW	21" x 15"	X		2.2							1	X															E-11
	89 " / 89 "	2' x 2'	X		4																							E-11
0.23 RT	EAST	2' x 1'			2											X												E-13
	63	2' x 2'			4																							E-13
	Y2	2' x 1'			2																							E-13
	14	2' x 2'			4																							E-13
	↑	21" x 15"			2.2																							E-13
0.25 LT.	STOP	30" x 30"	X		6.3										X													E-15C
	LEGAL LOAD LIMIT 24000	2' x 2'	X		4																							E-15A
0.26 RT.	STOP	2' x 2'	X		4									X														E-15C
	LEGAL LOAD LIMIT 24000	2' x 2'	X		4																							E-15C
0.27 RT.	5 BARRE 4	72" x 10"			5							2	X															E-23
	6 BARRE 6	72" x 10"			5																							E-23
0.31 RT.	PASS WITH CARE EXIST. / PASS WITH CARE NEW	3' x 3'	X		9									X(2)		X												TD 543
0.33 RT.	TO / 14 / ↑		X																									
0.35 LT.	END / 63		X																									
0.65 RT.	DO NOT PASS EXIST. / UNSAFE TO PASS NEW	3' x 3'	X		9									X(2)		X												TD 543
0.82 RT.	PASS WITH CARE EXIST. / PASS WITH CARE NEW	3' x 3'	X		9									X(2)		X												TD 543
0.90 LT.	LOWER TRAFFIC KEEP RIGHT	3' x 4'			12											X												E-15A
0.96 RT.	TRUCKS USE LOWER GEAR VACANT POST	3' x 3'	X		9									X(2)		X												E-19B
	NEXT 3 MILES	18" x 18"	X		2.3																							
0.00 (BERLIN) LT.	BERLIN BARRE				X																							STRAIGHTEN SIGN PAYMENT TO BE SUBSIDIARY TO OTHER ITEMS
0.09 RT.	DO NOT PASS / UNSAFE TO PASS	3' x 3'	X		9									X(2)		X												TD 543
0.22 RT.	TRUCKS USE LOWER GEAR VACANT POST		X											X														RETAIN POST FOR SEASONAL MOUNTING OF SNOWMOBILE CROSSING SIGN
0.55 LT.	TRUCKS USE LOWER GEAR VACANT POST		X											X														RETAIN POST FOR SEASONAL MOUNTING OF SNOWMOBILE CROSSING SIGN
TOTALS			19	X	138																							FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S 'SIGN POST DESIGN MANUAL'.

PREPARED BY S.M. DATE 1/30/86  
 CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 PROJ. BERLIN - BARRE  
 STATEWIDE NO. F-SFTY(85)  
 TRAFFIC SHEET NO. 538 SHEET 92 OF 200