TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS	EXISTING SIGNS TO BE SALVAGED: REMOVE (EA.)	REMOVE (X)	RETAIN (X)	NEW AND SALVAGED SIGNS: NEW "A" (S.F.)	NEW "B" (S.F.)	SALV. SIGN (EA.)	SALV. T.I.S. (S.F.)	EXISTING POSTS: RET.	DRILL	REM.	SALV.	NEW SIGN POSTS: NUMBER OF POSTS	FLANGED CHANNEL: 2.0 LB./FT.	2.5 LB./FT.	3.0 LB./FT.	TUBULAR ALUMINUM: 3.0" Ø	3.0" □	4.0" Ø	4.0" Ø MOD.	W SHAPED STEEL: POST SIZE	WEIGHT	FTG. SIZE 24"	FTG. SIZE 30"	REMARKS	FOR SIGN DETAIL SHEET: PLAN SHEET NUMBER	STD. SHEET NUMBER
1.26 Lt.	STOP				X					X																		
1.27 Lt.	STOP				X					X																		
1.27 Lt.	E. PITTSFORD 2 →				X					X(2)																		
1.27 Lt.	CHITTENDEN 6 →				X																							
1.27 Lt.	CHITTENDEN NATIONAL FISH GRAPE 8 →				X																							
1.27 Lt.	MEADOW LAKE RD.		1	X				1				X		1	X											Relocate For Better Visibility		
1.34 Lt.	E. PITTSFORD 2 ↱	72" X 10"				5.0								2	X													E-23
1.34 Lt.	CHITTENDEN 6 ↱	72" X 10"				5.0																						E-23
1.38 Lt.	MENDON RUTLAND 4				X					X																		
1.39 Lt.					X					X																		
1.40 Lt.			1									X																
1.42 Lt.	SCHOOL BUS STOP AREA				X					X																		
1.46 Lt.	TULIP TREE INN → 5	* 75" X 16"	* 1	* X					8.3			X		*2			X									*Note: All Quantities to be Included in T.I.S. = Item 680.20 MOD. (NON-PARTICIPATING)		
1.46 Lt.	MOUNTAINTOP INN → 5	* 75" X 16"	* 1	* X					8.3																	" " " "		
1.50 Lt.	Mt Top Ski Touring Ctr → 6				X					X(2)																		
1.55 Lt.	WATCH FOR TURNING VEH.				X					X																		
1.59 Lt.	STOP / LEGAL LOAD LIMIT	30" X 30"	1	X				1				X		1	X													
		24" X 24"	1	X				1																				
1.59 Rt.	TRUCK LANE 400 FEET	24" X 30"				5.0								1	X													E-15A
1.62 Lt.	MEDWAY RD		1	X				1				X		1	X													
1.69 Rt.	SLOWER TRAFFIC KEEP RIGHT	24" X 30"	1			5.0						X		1	X													E-15A
1.78 Lt.	DO NOT PASS		1									X																
1.78 Lt.	UNSAFE TO PASS	36" X 36"				9.0								1			X										TD 557	

TOTALS			7			29.0#		4	16.6#					8	184#		48#											

FINAL LENGTHS ARE TO BE DETERMINED IN THE FIELD, POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE DESIGN DIVISION'S "SIGN POST DESIGN MANUAL".

PREPARED BY JB DATE 1-86

CHECKED BY _____ DATE _____

PROJ. MENDON ~ SHERBURNE STATEWIDE NO. F-SFTY (85)S

TRAFFIC SHEET NO. 72546 SHEET 122 OF 200

1986