PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	OVERLAY DEPTH	LEVELING COURSE	GRAVEL SHOULDERS	GRAVEL SHOULDERS	EMULSIFIED ASPHALT	BITUMINOUS CONCRETE PAVEMENT	POWER BROOM RENTAL	CHANGE ELEV. OF CB, DI OR MH	UNIFORMED TRAFFIC OFFICERS	FLAGPERSONS	TOPSOIL		
							OPTION								
ITEM NO				402.10	402.11	404.65	406.25	608.30	604.40	630.10	630.15	653.10			
UNIT	FT.	FT.	IN.	TONS/MI.	CY.	TON	CWT	TON	HR.	EA.	HR.	HR.	CY		
LOCATION															
BRATTLEBORO US5 MM 4.519 ~ MM 4.652	702	50	1½	568			5	312	1	11	19	19			CURB to CURB ISLANDS
								76							LEVEL @ 568 TONS/MI.
BRATTLEBORO US5 MM 4.652 ~ MM 5.497	4462	24	1½	273			25	1652	7	0	94	94			8' PAVED SHOULDERS
								231							LEVEL @ 273 TONS/MI.
PROJECT					10	20	3	115	1	—	4	4	19		INCLS. DRIVES & APPROACHES
Rounding					—	—	2	24	1	—	3	3	1		
TOTALS					10	20	35	2410	10	11	120	120	20		

PROJECT BRATTLEBORO NO. M 200X(12) S SHEET 14 OF 23