

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS.	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			R.C.P. PIPES			M.E.S.	R.C.P.E.S.	CONC.	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 60440	SELECTIVE THINNING	GUARD RAIL ITEMS					DELINEATORS	REMARKS
		SMALL	LARGE						D	L	TH	D	L	CL							I	II				621.5	621.20	621.75	621.60	621.50		
3.94	RT.			10	10			5																			32	12.5	1		2	CONNECT GUARD RAIL APPROACH SECTION, TYPE I MOD. TO H.D. BEAM ON BRIDGE. CONNECT 112.5FT. OF NEW STEEL BEAM TO APPROACH SECTION. INSTALL BCT.
3.94	LT.																											12.5		2		CONNECT GUARD RAIL APPROACH SECTION TYPE I MOD. TO H.D. BEAM ON BRIDGE. CONNECT 12.5FT. OF NEW STEEL BEAM TO APPROACH SECTION. INSTALL BCT.
JOHNSON	TOTALS			10	10			5																			32	12.5	2	2	2	

JOHNSON
 1985 STATEWIDE SAFETY PROGRAM
 SHEET 47 OF 500