

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			RC PIPES			MES	RC PES	CONC	STEEL	REHAB DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 60440	SELECTIVE THINNING	GUARD RAIL ITEMS					DELINEATORS	REMARKS																														
		SMALL	LARGE						D	L	TH	D	L	CL							I	II				621.80	621.20	621.60	621.50																																	
3.63	RT				30	4			24	8	.064				1-24																	EXTEND PIPE 8'± ADD MES AND REGRADE SLOPE SEE DETAIL "B" SHEET 4																														
3.69	RT				30				60	48	.138											50			40							EXTEND PIPES 16'± USE EARTH BORROW AND STONE FILL TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4																														
4.10	RT				30																											USE EARTH BORROW TO COVER LEDGE OUTCROP																														
4.19	RT																															REMOVE EXISTING GUIDE POSTS COST TO BE SUBSIDIARY TO OTHER ITEMS IN CONTRACT																														
4.22	RT				40																											USE EARTH BORROW TO FLATTEN DRIVE SIDESLOPES SEE SHEET 5 FOR DETAILS																														
4.51	RT				10	2			15	8	.064																					EXTEND PIPE 8'± FLATTEN SLOPE WITH EARTH BORROW SEE DETAIL "A" SHEET 4																														
4.55	RT				10	2			15	8	.064																					EXTEND PIPE 8'± FLATTEN SLOPE WITH EARTH BORROW SEE DETAIL "A" SHEET 4																														
4.63	RT				30	2	2		42	10	.109				1-42																	REMOVE TOP OF HEADER, GROUT 42" PIPE INTO EXISTING CONC. BOX. USE 10'± NEW PIPE AND MES FLATTEN SIDE SLOPE WITH EARTH BORROW SEE DETAIL "B" SHEET 4																														
4.98	RT				20	2			48	8	.109				1-48																	EXTEND PIPE 8'± ADD MES USE EARTH BORROW TO FLATTEN SLOPE SEE SHEET "B" SHEET 4																														
3.62	LT				10										1-24"																	ADD MES TO PIPE AND FLATTEN SIDE SLOPE SEE DETAIL "B" SHEET 4																														
3.68	LT				30				60	48	.138											50			40							EXTEND PIPES 16'± USE EARTH BORROW AND STONE FILL TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4																														
3.72	LT				20	10		10	18	30	.064				2-18'																	USE NEW PIPE AND RECONSTRUCT DRIVE SEE DETAIL "D" SHEET 4																														
3.74	LT				15										2-24																	ADD END SECTIONS AND FLATTEN DRIVE SIDE SLOPES SEE DETAIL "D" SHEET 4																														
4.18	LT																															REMOVE LARGE GUIDE POSTS COST SUBSIDIARY TO OTHER ITEMS IN CONTRACT																														
4.62	LT				25	5	2		42	8	.109											10										REMOVE TOP OF HEADER, GROUT 42" PIPE INTO EXISTING CONC. BOX. USE 8'± NEW PIPE AND REGRADE AREA TO DRAIN SEE DETAIL "A" SHEET 4																														
4.97	LT				15				48	8	.109											5										EXTEND PIPE 8'± AND FLATTEN SLOPE SEE DETAIL "A" SHEET 4																														
NEW HAVEN TOTALS					315	27	4	10	15	16	.064				2-18							115			80																																					
									18	30	.064				4-24																																															
									24	8	.064				1-42																																															
									42	18	.109				1-48																																															
									48	16	.109																																																			
									60	96	.138																																																			