

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS	METAL PIPE			RC PIPES			MES	RCPE	CONC	STEEL	REHAB. DI.	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 60440	SELECTIVE THINNING	GUARD RAIL ITEMS					DELINEATORS	REMARKS
		SMALL	LARGE						D	L	TH	D	L	CL							I	II				62180			62120	62160	62190	
MENDON																																
3.81	LT				20	2	2					18	8	III																		REMOVE HEADWALL, EXTEND PIPE 8'+ FLATTEN SLOPE SEE DETAIL "A" SHEET 4
3.84	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
3.86	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
3.88	LT					2	2										2.0	200		1-B												REMOVE HEADWALL, OCNSTRUCT DI, REGRADE DITCH SEE DETAIL "E" SHEET 4
3.90	LT						4																									REMOVE HEADWALLS FROM DRIVE PIPE SEE DETAIL "C" SHEET 4
3.91	LT				15	4	4		15	16	.064																					REMOVE HEADWALL, EXTEND PIPE 8'± FLATTEN SIDESLOPE (BOTH SIDES OF DRIVE) SEE DETAIL "D" SHEET 4
3.93	LT				10	2	2										2.0	200		1-B												REMOVE HEADWALL, CONSTRUCT DROP INLET REGRADE DITCH SEE DETAIL "E" SHEET 4
3.99	LT				15	2	2		24	8	.064				1-18"																	REMOVE HEADWALL, EXTEND PIPE 8'±, ADD MES REGRADE SLOPE SEE DETAIL "B" SHEET 4
4.06	LT				15	2	2					24	8	III	1-18"																	REMOVE HEADWALL, EXTEND PIPE 8'±, ADD MES REGRADE SLOPE SEE DETAIL "B" SHEET 4
4.12	LT				20	2	2										2.0	200		1-B												REMOVE HEADWALL, CONSTRUCT DROP INLET REGRADE DITCH SEE DETAIL "E" SHEET 4
4.14	LT				15		2		15	8	.064				1-15																	REMOVE HEADWALL, EXTEND PIPE 8'± AND ADD MES REGRADE AREA SEE DETAIL "B" SHEET 4
4.15	LT				15	2	2										2.0	200		1-B												REMOVE HEADWALL, CONSTRUCT DROP INLET REGRAD DITCH SEE DETAIL "E" SHEET 4
4.21	LT				15	4	2		18	8	.064						3.0	300		1-B												REMOVE HEADWALL, EXTEND 18" PIPE 8', CONSTRUCT 11'X6' DROP INLET, REGRADE DITCH SEE DETAIL "E" SHEET 4
4.35	LT				5	2	2								1-18"																	REMOVE HEADWALL, ADD MES REGRADE AREA SEE DETAIL "B" SHEET 4
4.51	LT				10	2	2					18	8	III	1-18"																	REMOVE HEADWALL, EXTEND PIPE 8'±, ADD END SECTION REGRADE SLOPE SEE DETAIL "B" SHEET 4
4.54	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
4.58	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
4.61	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
4.63	LT				10	2	2										2.0	200		1-B												REMOVE HEADWALL, CONSTRUCT DROP INLET REGRADE DITCH SEE DETAIL "E" SHEET 4
4.66	LT				40	4	4		18	24	III				2-18"																	REMOVE HEADWALL, EXTEND PIPE 12'±, ADD MES, FLATTEN SIDE SLOPE (BOTH SIDES OF DRIVE) SEE DETAIL "D" SHEET 4
4.73	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
4.86	LT																		1													RECONSTRUCT DROP INLET
4.91	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
4.96	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
4.98	LT				15	2	2										2.0	200		1-B												REMOVE HEADWALL, CONSTRUCT DROP INLET, REGRADE DITCH SEE DETAIL "E" SHEET 4
5.05	LT				40	4	2					36	12	III																		REMOVE HEADWALL, EXTEND PIPE 12'± USE EARTH BORROW TO FLATTEN SLOPE SEE DETAIL "A" SHEET 4
5.36	LT				25	2	2										2.0	200		1-B												REMOVE HEADWALL, CONSTRUCT DROP INLET REGRADE DITCH SEE DETAIL "E" SHEET 4
5.48	LT				15	2	2										2.0	200		1-B												REMOVE HEADWALL, OCNSTRUCT DROP INLET, REGRADE DITCH SEE DETAIL "E" SHEET 4
SHEET TOTALS					300	42	60		15	24	.064	18	16	III	1-15	2-18	49.0	1900	1	9-B												
									18	32	.064	24	8	III	4-18																	
									24	8	.064	36	12	III																		