

1985 STATEWIDE SAFETY PROJECT ITEM DETAIL SHEET

MILE MARKER	POS	REMOVING TREES		UNCLASSIFIED EXCAVATION	EARTH BORROW	TRENCH EARTH	TRENCH ROCK	GRAVEL SHOULDERS		METAL PIPE			RC PIPES			MES	RC PES	CONC	STEEL	REHAB. DI	GRATE TYPE B	STONE FILL		TIMBER CURB	ITEM 604.40	SELECTIVE THINNING	GUARD RAIL ITEMS				DELINEATORS	REMARKS
		SMALL	LARGE					D	L	D	L	TH	D	L	CL							I	II				621.80	621.20	621.60	621.50		
MENDON																																
5.68	LT				15	2	2	24	8	.064					1-24"																	REMOVE HEADWALL, EXTEND PIPE 8± ADD MES AND FLATTEN SLOPE SEE DETAIL "B" SHEET 4
5.77	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
5.87	LT				15	2	2											2.0	200		1-8											REMOVE HEADWALL, CONSTRUCT DROP INLET, REGRADE DITCH SEE DETAIL "E" SHEET 4
5.92	LT				15	2	2					18	4	III				2.0	200		1-8											REMOVE HEADWALL, EXTEND PIPE 4±, CONSTRUCT DROP INLET REGRADE DITCH SEE DETAIL "E" SHEET 4
SHERBURN																																
0.02	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
0.16	LT						2																									REMOVE HEADWALL, FROM EAST SIDE OF DRIVE PIPE SEE DETAIL "C" SHEET 4
0.20	LT						2																									REMOVE HEADWALL SEE DETAIL "C" SHEET 4
0.33-0.44	LT							118																		590	650		2			EXTEND NEW GUARD RAIL 25'± IN EACH DIRECTION SEE SHEET 3 FOR DETAILS
0.58-0.65	LT							61																		335	375	1	1			WRAP WESTERLY END AROUND DRIVE AND EXTEND EASTERLY END 25'±- SEE SHEET 3 FOR DETAILS
0.83	LT				15															1												RECONSTRUCT DROP INLET REGRADE DITCH
0.91	LT				5															1												RECONSTRUCT DROP INLET REGRADE DITCH
0.98	LT				5															1												RECONSTRUCT DROP INLET REGRADE DITCH
1.21	LT						2																									REMOVE HEADWALL FROM EAST SIDE OF DRIVE PIPE SEE DETAIL "C" SHEET 4
1.50-1.54	LT					5																60										USE STONE FILL TO REGRADE DITCH
1.54	LT				5		2										1-36															REMOVE HEADWALL, ADD MES REGRADE SLOPE SEE DETAIL "B" SHEET 4
1.58	LT			5																												REMOVE BOULDER FROM DITCH
1.84-1.89								59																		305	325	1	1			WRAP WESTERLY END AROUND DRIVE SEE SHEET 3 FOR DETAILS
2.06-2.18								118																				650		2		NEW GUARD RAIL TO PROTECT SLOPE RAIL WILL END ON VT. 100 SEE SHEET 3 FOR DETAILS
SHEET TOTALS				5	75	11	18	356	24	8	.064	18	4	III	1-24" 1-36"		4.0	400	3	2-8	60					1230	2,000	2	6			