

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES														TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
ROADWAY	CHANNEL	SUPER STRUCTURE	ABUT 1	ABUT 2	APPR SLAB 1	APPR SLAB 2	TRAINING	EROSION CONTROL	FULL E&C	BRIDGE QUANTITY	FOUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS			
3												3		EACH	CAST IRON GRATE WITH FRAME, TYPE D	604.47						
2												2		EACH	CAST IRON COVER WITH FRAME	604.55						
5												5		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25						
100												100		MGAL	DUST CONTROL WITH WATER	609.10						
3												3		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15						
20								10				30		CY	STONE FILL, TYPE I	613.10						
								20				20		CY	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10						
								30				30		CY	STONE FILL, TYPE I (MOD. - CONSTRUCTION ENTRANCE)	613.10						
								10				10		CY	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10						
	550									550		550		CY	STONE FILL, TYPE III	613.12						
285												285		LF	VERTICAL GRANITE CURB	616.21						
19												19		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH (MOD.)	618.10						
3												3		EACH	YIELDING MARKER POSTS	619.17						
42												42		LF	GATE FOR CHAIN-LINK FENCE, 6 FEET	620.16						
4												4		EACH	BRACING ASSEMBLY FOR CHAIN-LINK FENCE, 6 FEET	620.21						
690												690		LF	REMOVAL OF EXISTING FENCE	620.55						
								1670				1670		LF	SNOW FENCE (MOD. - PDF)	620.70						
50												50		LF	SNOW BARRIER - GALVANIZED	620.75						
450												450		LF	MISCELLANEOUS FENCE (WOOD SPLIT RAIL)	620.80						
471												471		LF	HEAVY DUTY STEEL BEAM GUARD RAIL (GALVANIZED)	621.21						
4												4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60						
4												4		EACH	GUARD RAIL, APPR. SECTION, NETC 2 RAIL	621.72						
100												100		HR	FLAGGERS	630.15						
									1			1		LS	FIELD OFFICE-ENGINEERS	631.10						
									1			1		LS	TESTING EQUIPMENT - CONCRETE	631.16						
									1			1		LS	TESTING EQUIPMENT - BITUMINOUS	631.17						
									1			1		LU	FIELD OFFICE - TELEPHONE (N. A. B. I.)	631.25			N. A. B. I. = NOT A BID ITEM			
							520					520		HR	EMPLOYEE TRAINEESHIP	634.10						
1												1		LS	MOBILIZATION / DEMOBILIZATION	635.11						
1												1		LS	TRAFFIC CONTROL	641.10						
1730												1730		LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40						
1630												1630		LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41						
39												39		LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46						
17												17		EACH	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50						
40												40		SY	GEOTEXTILE FOR ROADBED SUBGRADE SEPARATOR (MOD.)	649.11						
			290	220						510		510		SY	GEOTEXTILE UNDER STONE FILL	649.31						
22												22		SY	GEOTEXTILE FOR UNDERDRAIN TRENCH LINING	649.41						
								450				450		SY	GEOTEXTILE FOR SILT FENCE	649.51						
			57	58						115		115		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61						
								100				100		LB	SEED	651.15						

PROJECT NAME: **READING**
 PROJECT NUMBER: **BRS 0148(6)S**
 FILE NAME: PW/85e034/Structures/s85e034qs.xls PLOT DATE: 11/30/2005
 PROJECT MANAGER: R. WHITCOMB DRAWN BY: L. BULLOCK
 DESIGNED BY: C. CARLSON CHECKED BY: C. CARLSON
 QUANTITY SHEET #2 SHEET 5 OF 83