STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
OPTION ITEMS																																			
14+60 LT	← FELCHVILLE 1	1	72	12	6.00						2			28			28	2															DI-1		E-123
	← SPRINGFIELD 13	1	72	12	6.00																												DI-1		E-123
	SO. WOODSTOCK 8 →	1	72	12	6.00																												DI-1		E-123
	WOODSTOCK 13 →	1	72	12	6.00																												DI-1		E-123
15+61 LT	FLAT IRON ROAD TH 5	2	30	9	3.75						1			14			14	1																	E-123
15+75 LT	↑	1	36	36	9.00						2			28			28	2															W3-1A		E-150
17+50 LT	JCT	1	15	21	2.19						2			28			28	2														X	M2-1		E-136B
	VERMONT 106	1	30	24	5.00																														E-136B
	END	1	24	12	2.00																												M4-6		E-140
	VERMONT 44	1	24	24	4.00																														E-136B
17+50 RT	SPEED LIMIT 50	1	24	30	5.00						1			14			14	1															R2-1		E-142
℄ 100+34 LT	STOP	1	30	30	~~5.18~~ 6.25						1			14			14	1															R1-1		E-143
	0440 1414 0010	1	6	10	0.42																														E-138
℄ 100+50 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1			14			14	1															VR-017		E-141
				SUBTOTAL	SF	SF	EA.	SF				FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB	EA.	EA.	LB					
				SIGN SHEET 2	65.54								140				140																		
				SIGN SHEET 1	42.74								98				98																		
				SUBTOTAL	108.28								238				238																		
				ROUNDING	0.72								2				2																		
				TOTAL	109.00								240				240																		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

SHEET NAME: SIGN SUMMARY SHEET #2
PROJECT NAME: READING
PROJECT NUMBER: BRS 0148(6)S
HIGHWAY NO.: VT 44
BRIDGE NO.: 1
OVER: THE MILL BROOK
FILE NAME: PW/85e034/Structures/se034sgn.dgn
PROJECT MANAGER: R. WHITCOMB
DESIGNED BY: C. CARLSON
BRIDGE SHEET NUMBER:
PLOT DATE: 17-FEB-2006
DRAWN BY: J. GILMORE
IPARM NAME: se034sg4.i
SHEET 39A OF 83