

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						820				820		CY	COMMON EXCAVATION	203.15				
								1300		1300		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
						32				32		CY	TRENCH EXCAVATION OF EARTH	204.20				
						1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								730		730		CY	STRUCTURE EXCAVATION	204.25				
								340		340		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						760				760		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						640				640		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
						35				35		CY	AGGREGATE SURFACE COURSE	401.10				
						75				75		CWT	EMULSIFIED ASPHALT	404.65				
						1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								119		119		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33				
								186		186		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10				
								330		330		LF	STEEL PILING, HP 12 X 74	505.16				
								2		2		EACH	DYNAMIC PILE LOADING TEST	505.45				
								30380		30380		LB	REINFORCING STEEL, LEVEL I	507.11				
								26050		26050		LB	REINFORCING STEEL, LEVEL II	507.12				
								275		275		SY	LONGITUDINAL DECK GROOVING	509.10				
								33		33		GAL	WATER REPELLENT, SILANE	514.10				
								70		70		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
								70		70		LF	JOINT SEALER, HOT Poured	524.11				
								155		155		LF	BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM	525.335				
								1		1		LS	TWO-WAY TEMPORARY BRIDGE (960 SF - EST.)	528.11				
								1		1		EACH	REMOVAL OF STRUCTURE (1320 SF - EST.)	529.15				
								16		16		EACH	BEARING DEVICE ASSEMBLY, STEEL REINFORCED ELASTOMERIC PAD	531.17				
													BEGIN OPTION AA					
						54				54		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215				
						54				54		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415				
						54				54		LF	18" CPEP(SL)	601.2615				
													END OPTION AA					
							10			10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
							1			1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
						50	10			60		CY	STONE FILL, TYPE I	613.10				
								980		980		CY	STONE FILL, TYPE IV	613.13				
						130				130		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
						270				270		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
						4				4		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
						4				4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM	621.725				

PROJECT NAME: **STOWE**
PROJECT NUMBER: **BRF 029 - 1(17)**
FILE NAME: s85e037qty.dgn
PROJECT LEADER: C. CARLSON
DESIGNED BY: H. I. SALLS
QUANTITY SHEET #1
PLOT DATE: 06/17/2013
DRAWN BY: G. ROY
CHECKED BY: H. I. SALLS
SHEET 4 OF 70