

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							350				350		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							50				50		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							500				500		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMobilIZATION	635.11				
							850				850		LF	4 INCH WHITE LINE	646.20				
							850				850		LF	4 INCH YELLOW LINE	646.21				
							20				20		LF	DURABLE 24 INCH STOP BAR	646.480				
							4				4		EACH	DURABLE LETTER OR SYMBOL	646.490				
							170		970		1140		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								183			183		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								110			110		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								30			30		LB	SEED	651.15				
								250			250		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								10			10		CY	TOPSOIL	651.35				
									390		390		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								50			50		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								1280			1280		SY	TEMPORARY EROSION MATTING	653.20				
								10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								18			18		CY	VEHICLE TRACKING PAD	653.35				
								1			1		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
								370			370		LF	BARRIER FENCE	653.50				
								780			780		LF	PROJECT DEMARCATION FENCE	653.55				
							11.08				11.08		SF	TRAFFIC SIGNS, TYPE A	675.20				
							132				132		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							8				8		EACH	REMOVING SIGNS	675.50				
							3				3		EACH	ERECTING SALVAGED SIGNS	675.60				
							1				1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									304		304		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT F BEAMS)(NEXT 36 F)	900.640				
							1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							562		24		586		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: **STOWE**
PROJECT NUMBER: **BRF 029 - 1(17)**
FILE NAME: s85e037qty.dgn
PROJECT LEADER: C. CARLSON
DESIGNED BY: H. I. SALLS
QUANTITY SHEET #2
PLOT DATE: 07/12/2013
DRAWN BY: G. ROY
CHECKED BY: H. I. SALLS
SHEET 5 OF 70