

QUANTITY SHEET 2



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES					
							ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS	
															END OPTION BB						
							9					9		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18					
							204					204		M	150 MM UNDERDRAIN PIPE	605.10					
							5					5		M	150 MM UNDERDRAIN CARRIER PIPE	605.20					
							5					5		EACH	UNDERDRAIN FLUSHING BASIN	605.95					
							10					10		HR	POWER GRADER RENTAL	608.15					
							10					10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25					
							2					2		T	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15					
							30					30		CM	STONE FILL, TYPE I	613.10					
							1070					1070		CM	STONE FILL, TYPE II	613.11					
										535		535		CM	STONE FILL, TYPE IV	613.13					
							78					78		M	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28					
							78					78		M	BITUMINOUS CONCRETE CURB, TYPE A	616.305					
							9					9		T	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47					
							2					2		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10					
							5					5		EACH	YIELDING MARKER POSTS	619.17					
							527					527		M	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21					
							77					77		M	HD STEEL BEAM GUARDRAIL, GALVANIZED W/2.4 M POSTS	621.215					
							4					4		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50					
							3					3		EACH	ENERGY ABSORPTION ATTENUATOR	621.56					
							2					2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60					
							4					4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED NETC 4 RAIL	621.73					
							300					300		M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80					
							590					590		M	TEMPORARY TRAFFIC BARRIER	621.90					
							430					430		M	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95					
							100					100		HR	UNIFORMED TRAFFIC OFFICERS	630.10					
							1000					1000		HR	FLAGGERS	630.15					
											1	1		LS	FIELD OFFICE, ENGINEERS	631.10					
											1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16					
											1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17					
											4000	4000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26					
								1040				1040		HR	EMPLOYEE TRAINEESHIP	634.10					
							1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11					
							1					1		LS	TRAFFIC CONTROL	641.10					
							1040					1040		M	DURABLE 100 MM WHITE LINE	646.400					
							1020					1020		M	DURABLE 100 MM YELLOW LINE	646.410					
							11					11		M	DURABLE 600 MM STOP BAR	646.480					
							4					4		EACH	DURABLE LETTER OR SYMBOL	646.490					
							1300					1300		M	TEMPORARY 100 MM WHITE LINE	646.600					
							1300					1300		M	TEMPORARY 100 MM YELLOW LINE	646.610					

PROJECT NAME: **STOCKBRIDGE**
 PROJECT NUMBER: **BRF 022-1(20)**
 FILE NAME: 05e039/Structures/de039excel.dgn PLOT DATE: 04/15/2010
 PROJECT LEADER: C.P.WILLIAMS DRAWN BY: D.D.BEARD
 DESIGNED BY: R.S.YOUNG CHECKED BY: H.I.SALLS
 QUANTITY SHEET #2 SHEET 6 OF 139