



**STOP ROADWAY
BEGIN BRIDGE
STA 10+175.058**

**END BRIDGE
RESUME ROADWAY
STA 10+221.658**

**ROAD
CLOSED**

ONE WAY →

MATCHLINE STA. 10+120

MATCHLINE STA. 10+275

MATCHLINE STA. 20+045

SIGNS TO BE LOCATED AS PER
STANDARDS E-100 & E-107

LEGEND

- ⊕ - SIGN POSTS
- ▣ - TYPE III BARRICADES (MOD.)
- ▬ - TEMP. TRAFFIC BARRIER
- ⊕ - RETROREFLECTORIZED BARREL
- - - - TEMPORARY STEEL SHEET PILING
- ~~~~~ - PAVEMENT MARKING REMOVAL

SPECIAL PROVISION
(TEMPORARY STEEL SHEET PILING)
STA 10+260.00 - 10+275.00 RT

REMOVE AND RESET TEMPORARY TRAFFIC BARRIER
REMOVE STA 10+250.00 - 10+275.00 RT
RESET TO STA 10+250.00 - 10+275.00 RT

TEMPORARY 100 mm WHITE LINE
STA 10+120.00 - 10+275.00 LT (2)

TEMPORARY TRAFFIC BARRIER
STA 10+120.00 - 10+275.00 CL

TEMPORARY 100 mm YELLOW LINE
STA 10+120.00 - 10+275 LT (DBL)



**PHASE B
TRAFFIC CONTROL
LAYOUT 3**

PROJECT NAME: STOCKBRIDGE
PROJECT NUMBER: BRP 022-1 (20)

FILE NAME: /str4/85e039/de039bdr.dgn PLOT DATE: 08-APR-2010
PROJECT LEADER: C.P. Williams DRAWN BY: H.I. SALLS
DESIGNED BY: H.I. SALLS CHECKED BY: R.S. Young
TRAFFIC CONTROL SHEET 34 OF 139