

GZA		Stockbridge BRF 022-1(20) SC		Boring No.: B-9		
GeoEnvironmental, Inc.		Stockbridge, Vermont		Page: 2 of 3		
Engineers and Scientists				File No.: 22721.4		
				Check: DGL/JLH		
Depth (m)	Sample Information					Equipment Installed
	No.	Pen./ Rec. (m)	Depth (m)	Blows (0.15m)	N Value	
	S-7	0.61/ 0.53	10.67- 11.26	8-12 16-20	28	Very stiff, gray, varved SILT & CLAY, trace fine Sand. (A-4)
	S-8	0.61/ 0.61	12.19- 12.80	19-27 26-20	58	Hard, gray, varved Clayey SILT, trace fine Sand. (A-4)
	S-9A/B	0.61/ 0.20	13.72- 14.33	21-21 20-50/127mm	41	S-9A: Dense, brown, fine to coarse SAND, little Gravel, little Silt. (A-2-4) S-9B: Dense, gray, SILT and fine Sand. (A-4)
15						Top of rock at 14.63 meters (48 feet). Refer to Core Boring Report pg 3.
20						
25						
REMARKS CORE LOG WELL: BR0221A1 GZA, N410307 1/2004						
All depth measurements are approximate. Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.						Boring No.: B-9

GZA		Stockbridge BRF 022-1(20) SC		Boring No.: B-9		
GeoEnvironmental, Inc.		Stockbridge, Vermont		Page: 3 of 3		
Engineers and Scientists				File No.: 22721.4		
				Check: DGL/JLH		
Depth (m)	CORE BORING REPORT					Equipment Installed
	Run No.	Depth (m)	Drilling Rate (min/ 0.30m)	Rec./ RQD (m)	Rec./ RQD (%)	
	C-1	15.24- 16.76	3	1.50/ 1.27	98/ 83	Hard, slightly weathered, grayish blue, fine-grained SCHIST, slightly fractured to massive.
	C-2	16.76- 18.34	4	1.57/ 1.52	100/ 97	Hard, fresh, grayish blue, fine-grained SCHIST, slightly fractured to massive.
						Bottom of boring at 18.29 meters (60 feet) below ground surface.
20						
25						
REMARKS CORE LOG WELL: BR0221A1 GZA, N410307 1/2004						
All depth measurements are approximate. Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.						Boring No.: B-9

GZA		Stockbridge BRF 022-1(20) SC		Boring No.: B-10		
GeoEnvironmental, Inc.		Stockbridge, Vermont		Page: 1 of 2		
Engineers and Scientists				File No.: 22721.4		
				Check: DGL/JLH		
Contractor: New Hampshire Boring		Auger/ Casing: S. Garside		Sampler: SS		
Foreman: Seth Currier		Type: HW		GROUNDWATER READINGS		
Date Start/Finish: 3-1-02 / 3-1-02		I.D.: 102 mm		Date		
Boring Location: 10+169, 10m L		Hammer Wt.: 136.1 kg		Time		
GS Elev.: 205.45m Datum: NAVD		Hammer Fall: 0.61 m		Depth		
		Rig Type: CME 650 ATV		Casing		
				Slab		
				No Measurements Taken		
Depth (m)	Sample Information					Equipment Installed
	No.	Pen./ Rec. (m)	Depth (m)	Blows (0.15m)	N Value	
	S-2	0.61/ 0.25	1.52- 2.13	15-9 8-6	17	Medium dense, brown, fine to coarse SAND, some Gravel, little Silt. (A-2-4)
	S-3	0.61/ 0.13	3.05- 3.86	8-10 12-10	22	Very stiff, gray, SILT & CLAY, some Gravel. (A-4)
	S-4	0.61/ 0.58	4.57- 5.18	5-11 16-19	27	Very stiff, gray, Clayey SILT. (A-4)
	S-5	0.05/ 0.05	6.10- 6.15	50/51mm	>100	Hard, gray, SILT & CLAY, trace weathered Rock. (A-4) Top of rock at 6.16 meters (20.2 feet). Refer to Core Boring Report pg 2.
5						
10						
15						
20						
25						
REMARKS CORE LOG WELL: BR0221A1 GZA, N410307 1/2004						
1. Sample S-2 was tested for electrochemical properties. 2. A grain-size distribution analysis and Atterberg limit tests were conducted on sample S-4.						Boring No.: B-10
All depth measurements are approximate. Stratification lines represent approximate boundary between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations of groundwater may occur due to other factors than those present at the time measurements were made.						Boring No.: B-10