

<b>GZA</b> GeoEnvironmental, Inc. Engineers and Scientists		Stockbridge BRF 022-1(20) SC Stockbridge, Vermont				Boring No.: B-13
						Page: 2 of 2
						File No.: 22721.4
						Check: DGL/JLH
<b>CORE BORING REPORT</b>						
Depth (m)	Sample Information		Sample Description & Classification		Stratum Desc.	Remarks
	Run No.	Depth (m)	Drilling Rate (min/0.30m)	Rec./RQD (m)	Rec./RQD (%)	Equipment Installed
	C-1	7.32-8.84	1 1.25 1.75 1.25 3.25	0.23/0.23	15/15	Hard, fresh, grayish blue, fine-grained SCHIST, very highly fractured.
	C-2	8.84-10.36	3.0 4.0 3.25 3.0 3.0	1.45/1.32	95/87	Hard, fresh, grayish blue, fine-grained SCHIST, slightly fractured to massive.
						Bottom of boring at approximately 10.36 meters below ground surface.
						Boring No.: B-13

<b>GZA</b> GeoEnvironmental, Inc. Engineers and Scientists		Stockbridge BRF 022-1(20) SC Stockbridge, Vermont				Boring No.: B-14
						Page: 1 of 2
						File No.: 22721.4
						Check: DGL/JLH
<b>CORE BORING REPORT</b>						
Depth (m)	Sample Information		Sample Description & Classification		Stratum Desc.	Remarks
	Run No.	Depth (m)	Drilling Rate (min/0.30m)	Rec./RQD (m)	Rec./RQD (%)	Equipment Installed
	S-1	0.61/0.20	0.00-0.61	1-1 1-1	2	Very loose, dark brown, fine to medium SAND and SILT, trace Organics, root fibers and grass. Moist. (A-2-5)
	S-2A/B	0.61/0.28	1.22-1.83	13-19 21-27	40	Top 0.03 m: Same as above. S-2A (Middle 0.08 m): Very dense, brown, fine to medium SAND, some SILT, trace Gravel. Dry. (A-2-4) S-2B (Bottom 0.18 m): Very dense, gray, fine to coarse SAND, some Gravel, little SILT, weathered rock. Dry. (A-2-4)
	S-3	0.61/0.53	2.74-3.35	4-9 10-13	19	Very stiff, gray, CLAY & SILT. Dry. (A-6)
	S-4	0.61/0.48	4.27-4.88	4-4 6-7	10	Stiff, gray, SILT & CLAY. Dry. (A-6)
	S-5A/B	0.61/0.53	5.79-6.40	15-19 21-26	40	Top 0.36m: Very stiff, CLAY & SILT, little fine to medium SAND. Dry. (A-6) Bottom 0.18m: Dense, gray and brown, fine to coarse SAND, some deintergraded rock, some SILT & Clay. Dry. (A-2-4) Advanced roller bit from 6.40 meters to 7.01 meters below ground surface. Top of rock at 6.70 meters. Refer to Core Boring Report pg 2.
						Boring No.: B-14

<b>GZA</b> GeoEnvironmental, Inc. Engineers and Scientists		Stockbridge BRF 022-1(20) SC Stockbridge, Vermont				Boring No.: B-14
						Page: 2 of 2
						File No.: 22721.4
						Check: DGL/JLH
<b>CORE BORING REPORT</b>						
Depth (m)	Sample Information		Sample Description & Classification		Stratum Desc.	Remarks
	Run No.	Depth (m)	Drilling Rate (min/0.30m)	Rec./RQD (m)	Rec./RQD (%)	Equipment Installed
	C-1	7.01-8.53	2.75 3.0 2.0 3.25 3.0	1.22/1.22	90/80	Moderately hard, fresh, grayish-blue, fine-grained, SCHIST, slightly fractured to massive.
						Bottom of boring at approximately 8.53 meters below ground surface.
						Boring No.: B-14