



SOUTH LINCOLN PARTNERSHIP LLC

5 VT RTE 125 @
CURVE #2 DATA
 $\Delta = 12^{\circ}31'04.0''$ LT
 R = 860 000
 T = 94 320
 L = 187+890
 E = 5 157
 BANK = VARIES

CLEAR AND GRUB TREES MAXIMUM OF
1500 FROM LIMIT OF CUT AND FILL
INSTALL AND MAINTAIN PROJECT
DEMARICATION FENCING OR BARRIER
FENCE AS INDICATED ON THE EPSC
CONSTRUCTION CONDITIONS SHEETS (TYPICAL)

CUSHING FAMILY, LLC
TREES AND OVERGROWN PASTURE LAND

LINES SHOWN ON THIS PLAN AS EXISTING
PROPERTY LINES P/L ARE BELIEVED TO
BE ACCURATE BUT SHOULD NOT BE RELIED
UPON FOR PURPOSES UNRELATED TO THE
STATE OF VERMONT'S ACQUISITION OF LAND
AND RIGHTS FOR THIS PROJECT.

NOTE: TO ALLOW FOR SETTLEMENT THE CONTRACTOR SHALL NOT PERFORM PAVING OPERATIONS
BETWEEN STATIONS 1+280 ~ 1+330 UNTIL A WAITING PERIOD OF 60 DAYS HAS PASSED
AFTER THE CONSTRUCTION OF THE EMBANKMENTS AND SUBBASE. UPON COMPLETION OF THE
60-DAY SETTLEMENT WAITING PERIOD THE CONTRACTOR SHALL VERIFY AND RE-ESTABLISH
SUBGRADE ELEVATIONS AS NECESSARY OR AS DIRECTED BY THE RESIDENT ENGINEER.
PAVING OPERATIONS SHALL ONLY BE ALLOWED PRIOR TO THE END OF THE 60-DAY WAITING
PERIOD IF THE CONTRACTOR OBTAINS SUFFICIENT SETTLEMENT DATA THAT INDICATES
INSIGNIFICANT SETTLEMENT AND ONLY WHEN IT IS APPROVED BY THE RESIDENT ENGINEER.

THE COST OF FURNISHING, INSTALLING, MONITORING AND MAINTAINING SETTLEMENT
MONITORING EQUIPMENT SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT AS A WHOLE
AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR VARIOUS ITEMS INVOLVED IN
THE CONTRACT.



FOR R.O.W. USE ONLY

DATUM	
VERTICAL	NAVD 88
HORIZONTAL	NAD 83(92)

PROJECT: CORNWALL	PROJECT NO.: BRS 0172(6)
DESIGN FILE NAME: IPARM FILE NAME:	PLOT DATE: 16-FEB-2010
SURVEYED BY: VTRANS & VT SURVEY	SURVEY DATE: 1996&1999
SQUAD LEADER: MARTHA EVANS-MONGEON	DRAWN BY: ERIK ATKINS
RIGHT OF WAY LAYOUT SHEET 3	SHEET: 115 OF 144