STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS: EA	SIGN DIMENSIONS: WIDTH (mm)	SIGN DIMENSIONS: HEIGHT (mm)	NEW & SALVAGED SIGNS: "A"	NEW & SALVAGED SIGNS: "B"	NEW & SALVAGED SIGNS: SALV SIGN	NEW & SALVAGED SIGNS: SALV TIS	EXIST POST: RETAIN	EXIST POST: SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 2.8	SQUARE STEEL (mm) 50 kg/m 3.6	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SHEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS (SHS = STANDARD HIGHWAY SIGN)	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STD. SHEET NUMBER
												OPTION ITEMS																							
1·259 RT			450	600	0.270						1					4.19		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER		SHS
1·261 RT			450	600	0.270						1					4.19		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER		SHS
1·279 RT			450	600	0.270						1					4.19		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER		SHS
1·281 RT			450	600	0.270						1					4.19		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER		SHS
1·299 RT			450	600	0.270						1					3.89		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER		SHS
1·301 RT			450	600	0.270						1					3.89		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER		SHS
1·320 RT			450	600	0.270						1					3.96 2.74		1															W1-8 FLUORESCENT YELLOW SHEETING TYPE VII OR HIGHER Post replaced 06-28-11 due to plow damage		SHS
1·343 RT	1250 0104 0060		150	250	0.038						1					2.36		1															E-138		
1·420 LT			750	750	0.563						1					4.72		1															W1-10R		SHS
	30 MPH		450	450	0.203	[illegible] 4-23-12																											W13-1 SUBMOUNT W/ PREVIOUS SIGN		SHS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
SHEET 2 TOTALS		m² 2.694	m² [illegible] 4-23-12	EA.	m²							m				m 38.32				kg			EA.	kg				EA.	EA.	kg					

PROJECT: CORNWALL
PROJECT NO.: BRS 0172(6)
DESIGN FILE NAME: z85e042tssum.dgn
IPARM FILE NAME:
SURVEYED BY: VTRANS & VTSURVEY
Prepared By: Joe Knipes
TRAFFIC SIGN SUMMARY SHEET 2
PLOT DATE: 11-APR-2012
SURVEY DATE: 1996&1999
Checked By:
SHEET: 2 OF 3