PROJECT [illegible] ROUTE [illegible] PROJECT NUMBER [illegible]

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT	QUANTITY	QUANTITY RT	
2.759	2.87	DASH	SOLID	146		586	732
2.87	3.422	SOLID	SOLID	2914		2914	5828
							6560
					- 4TH. X 40	X 2 =	-320
							6240
		ASSUME 100% IS LOST DURING SHIMMING					
		2 X 6240 = 12480					12480

TEMPORARY 4" REFLECTORIZED WHITE LINE

MILE	MILE	LT	RT				
2.759	3.422	SOLID	SOLID	3501		3501	7002