TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT		QUANTITY RT	
JOHNSON							
3.927	4.277	S	S	1548		1845	3393
	MINUS 2 ROADWAY OPENINGS AT 40' EACH					=	-160
		2 x 40 x 2 = 160'					
					SUB-TOTAL =		3536
	ASSUME 75% LOST DUE TO LEVELING					=	2652
					SUB-TOTAL =		6188
					ROUNDING		12
					TOTAL =		6200

TEMPORARY 4" REFLECTORIZED WHITE LINE

JOHNSON							
3.927	4.277	S	S	1548		1845	3393
					ROUNDING		7
					TOTAL		3400

SHEET 17 OF 31