PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH	WIDTH	MOBILIZATION	ALL PURPOSE EXCAVATION RENTAL, TYPE I	TEMPORARY PAVEMENT MARKING 4" (YELLOW)	TEMPORARY PAVEMENT MARKING (WHITE) 4"	DURABLE 24" STOP BAR	DURABLE LETTER WORD MARKING	TRAFFIC SIGNS, TYPE A	TRAFFIC SIGNS POST TYPE A	PAINTED CURB	DUR. 4" REFLECT. WHITE LINE
ITEM NO			635.10	608.25	646.36	646.35	646.64	646.66	675.20	675.35	646.21	646.60
UNIT	FT.	FT	LS	HRS.	FT.	FT.	LF	EA.	SF	lbs.	LF	LF
LOCATION												
Pawlet HMA 2629			0.08	10	15000	11500	15	13	9	24	—	—
WELLS-Poultney HMA 2650			0.35	10	73600	52400	—	—	—	—	—	—
WELLS-POULTNEY-CASTLETON HMA2628			0.57	10	110,100	85500	—	24	—	—	1050	600
TOTALS			1	30	198700	149400	15	37	9	24	1050	600

COMPOSITE PROJECT PAWLET, WELLS POULTNEY, CASTLETON NO. HMA2628, HMA2629 HMA2650 SHEET 3A OF 35