PROJECT: PAWLET ROUTE VT 149 PROJECT No. HMA 2629

TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	QUANTITY LT	QUANTITY CL	QUANTITY RT	TOTAL
0.00	0.26	SOLID	SOLID	1373.		1373.	2746.
0.26	0.398	DASH	SOLID	182.		729.	911.
							3,657.
		ASSUME 75% ¢ IS LOST DURING SHIMMING					
		3,657 X 175% = 6,400 LS.					
TEMPORARY 4" REFLECTORIZED WHITE LINE							
0.00	0.398			2,101.		2,101.	4,202.