

PROJECT LENGTHS AND ITEM QUANTITIES

ITEM DESCRIPTION	LENGTH		WIDTH TRAVELED WAY		OVERLAY DEPTH		LEVELING COURSE		EMULSIFIED ASPHALT		BETUMINOUS CONCRETE		POWER BROOM RENTAL		UNIFORMED TRAFFIC OFFICERS	
	FT.	IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.	TONS/IN.
ITEM NUMBER					402.10	402.11	404.65	406.25	608.30	630.10	630.15					
UNIT	FT.	IN.	TONS/IN.	TONS/IN.	CY.	TON	CWT.	TON	HR.	HRS.	HRS.					
LOCATION																
WELLS Vt. 30	6600'	22"	3/4"	250	50	88	22	733								1' PAVED SHOULDER
Poultney Vt. 30	10402'	24"	3/4"	200	193	337	34	1155								LEVEL @ 250 TONS/IN.
Poultney Vt. 30	1293'	24"	3/4"	218	144	252	4	144								GRAVEL SHOULDER
Poultney Vt. 30	1827'	24"	3/4"	218	34	59	6	203								6' GRAVEL SHOULDER
Poultney Vt. 30	11326'	22"	3/4"	200	210	367	34	1154								LEVEL @ 213 TONS/IN.
CASTLETON Vt. 20	7181'	24"	3/4"	218	133	233	24	798								1' GRAVEL SHOULDER
CASTLETON Vt. 30	1594'	24"	1 1/4"	164	30	52	5	295								LEVEL @ 272 TONS/IN.
CASTLETON Vt. 30	596'	38"	1 1/4"	259	-	-	4	212								4' PAVED SHOULDER
CASTLETON Vt. 30	1125'	46"	1 1/4"	314	-	-	9	486								5' PAVED SHOULDER
CASTLETON Vt. 30	829'	24"	1 1/4"	164	-	-	4	205								4' PAVED SHOULDER
								26								LEVEL @ 164 TONS/IN.
PROJECT					100	175	3	100	65	365	365					0.25 HRS
ROUNDING					36	12	1	59	5	10	10					
TOTAL	42773				930	1575	150	7350	70	375	375					

PROJECT WELLS-POULTNEY-CASTLETON

NO. HMA 2628
SHEET 21 OF 35 SHEETS