

WELLS-POULTNEY
PROJECT: CASTLETON ROUTE VT 30 PROJECT No. HMA 2628
TEMPORARY 4" REFLECTORIZED YELLOW LINE

MILE	MILE	LT	RT	QUANTITY		QUANTITY	TOTAL
				LT	CL	RT	
2.393	3.643	SOLID	SOLID	6600.		6600.	13200.
4.885	5.36	SOLID	SOLID	2508.		2508.	5016.
5.36	5.48	SOLID	DASH	634.		158.	792.
5.48	5.54	SOLID	SOLID	317.		317.	634.
5.54	5.59	DASH	SOLID	46.		264.	330.
5.59	5.66	DASH	DASH		370.		370.
5.66	5.79	SOLID	DASH	686.		172.	858.
5.79	5.90	DASH	DASH		145.		145.
5.90	6.05	DASH	SOLID	198.		792.	990.
6.05	6.23	SOLID	DASH	950.		238.	1188.
6.23	6.43	DASH	SOLID	264.		1056.	1320.
6.43	6.61	SOLID	SOLID	950.		950.	1900.
6.61	6.73	SOLID	DASH	634.		158.	792.
6.73	6.95	SOLID	SOLID	1162.		1162.	2324.
6.95	7.11	DASH	SOLID	211.		845.	1056.
7.11	9.26	SOLID	SOLID	11,352.		11,352.	22,704.
9.26	9.44	SOLID	DASH	950.		238.	1,188.
9.44	9.59	DASH	DASH		198.		198.
TOWN LINE							
0.00	0.03	DASH	DASH		40.		40.
0.03	0.20	DASH	SOLID	224.		898.	1,122.
0.20	0.60	SOLID	SOLID	2,112.		2,112.	4,224.
0.60	0.73	SOLID	DASH	686.		172.	858.
0.73	1.04	DASH	DASH		409.		409.
1.04	1.18	DASH	SOLID	185.		739.	924.
1.18	1.36	SOLID	SOLID	1,478.		1,478.	2,956.
1.36	1.56	DO NOT PAVE - NO MATERIAL REQUIRED					0000
1.56	2.32	SOLID	SOLID	4,013.		4,013.	8,026.
2.32	2.34	SOLID	DASH	106.		26.	132.
ASSUME 50% IS LOST DURING SHIMMING							73696.
						6TH.	480
150% X 72640 = 108,960 LBS.					TOTAL		110,064
TEMPORARY 4" REFLECTORIZED WHITE LINE							
2.393	3.643	SOLID	SOLID	6600.		6600.	13200.
4.885	9.59	SOLID	SOLID	24,842.		24,842.	49,684.
0.00	1.36	SOLID	SOLID	7,181.		7,181.	14,362.
1.56	2.34	SOLID	SOLID	4,118.		4,118.	8,236.
					TOTAL		85,482.