STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

VAST Metric

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (mm) 44 (2.8 kg/m)	50 (3.6 kg/m)	63 (5.0 kg/m)	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia.(mm) 75 (1.9 kg/m)	100.0 (2.5 kg/m)	100 MOD (2.5 kg/m)	TUBULAR STEEL dia.(mm) FOUNDATION	75 (11.3 kg/m)	89 (13.4 kg/m)	100 (16.1 kg/m)	125 (21.8 kg/m)	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
STA. 2+138.1, RT.	ONE WAY B-B	1	900	300	0.27						2		8.7		2															R6-1L		SHS
	ONE WAY	1	900	300	0.27																									R6-1R		SHS
	DO NOT ENTER	1	750	750	0.56																									R5-1		SHS
	END ONE WAY B-B	1	750	900	0.68																									R6-7 MOUNT ONE WAY SIGNS BACK TO BACK ABOVE LEGAL LOAD LIMIT AND END ONE WAY SIGN		SHS
STA. 2+154.7, LT.	STOP	1	750	750	0.56						1		4.2		1															R1-1		SHS
STA. 2+162.7, RT.	NOT THIS WAY	1	300	450	0.14						1		3.9		1																SGD-1	
STA. 2+209.1, LT.	JOE'S BROOK RD	1	900	230	0.21						1		3.7		1																	E-123
STA. 2+209.7, RT.		1	750	750	0.56						1		4.2		1															W11-2 (FYG)		SHS
		1	600	300	0.18																									W16-7PL (FYG		SHS
STA. 2+212.4, LT.		1	750	750	0.56						1		4.2		1															W11-2 (FYG)		SHS
		1	600	300	0.18																									W16-7PL (FYG		SHS
STA. 2+217.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1		4.2		1																	E-141
STA. 2+239.4, RT.	SPEED LIMIT 30	1	600	750	0.45						1		4.2		1															R2-1 (30)		SHS
HILL ST. STA. 3+013.0, LT.	RT 2.1 HILL ST	1	600	230	0.14						1		3.9		1																	E-123
		1	600	230	0.14																											
STA. 3+028.0, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1		4.2		1																	E-141
PEACHAM RD. STA. 4+024.0, RT.	RT 2.1 PEACHAM RD	1	600	230	0.14						1		3.9		1																	E-123
		1	750	230	0.17																											
STA. 4+089.4, RT.		1	600	600	0.36						1		4.1		1															R3-1		SHS
												m 0	m 53.4	m 0		EA	kg	kg	kg		kg	kg	kg	kg								
SHEET TOTALS					m² 6.47	m²	EA.	m²					m 53.4					kg			EA.		kg			EA.	EA.	kg					

NOTES:
1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS 'SIGN POST DESIGN GUIDELINE.'
2. ALL OVERHEAD GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE IX BACKGROUND. ALL GROUND MOUNTED GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE III BACKGROUND. ALL CHEVRON SIGNS SHALL HAVE TYPE IX SHEETING. ALL OTHER GROUND MOUNTED SIGNS SHALL HAVE A MINIMUM TYPE III SHEETING.

FYG = FLUORESCENT YELLOW GREEN

Stantec

PROJECT NAME: DANVILLE
PROJECT NUMBER: F EGC 028-3(32)

FILE NAME: ...\traffic sign summary.ptf
DESIGN SUPERVISOR: GARY SANTY
DESIGNED BY: STANTEC
TRAFFIC SIGN SUMMARY SHEET TSS-7

PLOT DATE: 1/18/2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 162 OF 306

1/18/2011 1:53:25 PM v:\1953\active\1953003_0092\highway\plotfiles\traffic sign summary.ptf