STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

VAST Metric

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.6	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM dia.(mm) 75 kg/m 1.9	100.0 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL dia.(mm) FOUNDATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
HIGHLAND AVE.	RT 2 E / Highland Ave	1	600	230	0.14																											E-123
		1	750	230	0.17						2		8.7		2															INSTALL STREET SIGNS ABOVE STOP SIGN USING POST TOP MOUNTING BRACKET		E-123
STA. 6+012.5, LT.	STOP	1	750	750	0.56																									R1-1		SHS
STA. 6+016.3, RT.	T HWY 04 / LEGAL LOAD LIMIT 24,000 POUNDS / SPEED LIMIT 25	1	650	750	0.45		1				2		9.6		2															R2-1 (25)		SHS
		1	600	750	0.45																											E-141
MOUNTAIN VIEW DR.	RT 2 E / Mountain View Dr	1	600	230	0.14																											E-123
		1	900	230	0.21						2		8.5		2															INSTALL STREET SIGNS ABOVE STOP SIGN USING POST TOP MOUNTING BRACKET		E-123
STA. 7+012.3, LT.	STOP	1	750	750	0.56																									R1-1		SHS
STA. 7+012.3, RT.	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1		3.8		1																	E-141
	TSSS 1 TOTALS				6.42	0	3					6.8	52.3	8.7 (NP)																		
	TSSS 2 TOTALS				7.51 2.16 (NP)	0 0	1 1 (NP)				2	0 0	64.9 0	0 8.7 (NP)																		
	TSSS 3 TOTALS				6.79	3.96	1				1	0	43.5	0				27.0														
	TSSS 4 TOTALS				7.35	2.84	0					0	64.7	0			18.2															
	TSSS 5 TOTALS				5.72 0	0 0	3 3 (NP)					3.4	51.2 0	0 8.7 (NP)																		
	TSSS 6 TOTALS				7.24	0	1					0	54.3	0																		
	TSSS 7 TOTALS				6.47	0	0					0	53.4	0																		
	TSSS 8 TOTALS				6.47	0	0					0	41.6	0																		
	TSSS 9 TOTALS				3.13	0	1					0	30.6	0																		
	SUBTOTALS				57.1	6.8	10					10.2	456.5	0			18.2	27.0														
	ROUNDING				0.9	0.2	0					0.8	0.5	0			0.8	0														
	TOTALS				58	7	10					11	457	0			19	27														
	NON-PARTICIPATING SUBTOTALS				2.16	0	4				3	0	0	26.1																		
	NON-PARTICIPATING ROUNDING				0.84	0	0				0	0	0	0.9																		
	NON-PARTICIPATING TOTALS				3	0	4				3	0	0	27																		
	SHEET TOTALS				m²	m²	EA.	m²				m	m	m		EA	kg	kg	kg		kg	kg	kg	kg	EA.	EA.	kg					

NOTES;

1. FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS 'SIGN POST DESIGN GUIDELINE.'
2. ALL OVERHEAD GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE IX BACKGROUND. ALL GROUND MOUNTED GUIDE SIGNS SHALL HAVE A MINIMUM TYPE IX LEGEND ON TYPE III BACKGROUND. ALL CHEVRON SIGNS SHALL HAVE TYPE IX SHEETING. ALL OTHER GROUND MOUNTED SIGNS SHALL HAVE A MINIMUM TYPE III SHEETING.

FYG = FLUORESCENT YELLOW GREEN

Stantec

PROJECT NAME: DANVILLE
PROJECT NUMBER: F EGC 028-3(32)

FILE NAME: ...\traffic sign summary.ptf
DESIGN SUPERVISOR: GARY SANTY
DESIGNED BY: STANTEC
TRAFFIC SIGN SUMMARY SHEET TSS-9

PLOT DATE: 1/18/2011
DRAWN BY: STANTEC
CHECKED BY: STANTEC
SHEET 164 OF 306

1/18/2011 1:53:27 PM v:\0953\active\053003.1092\highway\plotfiles\traffic sign summary.ptf