QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

APPROXIMATE SUMMARY OF QUANTITIES

LUDLOW BR 99	MT. HOLLY BR 33	LUDLOW VT 103	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
20			20	CY	UNCLASSIFIED EXCAVATION	203.17	
200	180		380	SY	COLD PLANING-BIT. PAVEMENT	210.10	
10			10	CY	SUBBASE OF GRAVEL	301.15	
					OPTION		
		65	65	CY	AGGREGATE SHOULDERS IN PLACE	402.10	6
		110	110		AGGREGATE SHOULDERS	402.12	7
		40	40	CWT	EMULSIFIED ASPHALT	404.65	2
100	70	3180	3350	TON	BITUMINOUS CONCRETE PAVEMENT	406.25	34
40	20		60	SY	PREPARATION OF CONCRETE SURFACE CLASS I (MOD.)	501.45	
100	100		200	SY	PREPARATION OF CONCRETE SURFACE CLASS II (MOD.)	501.46	
150	140		290	SF	SURFACE PREPARATION FOR MEMBRANE	501.49	
1	1		2	CF	CONCRETE CLASS AA (QUICK SETTING)	501.52	
300	300		600	LBS	REINFORCING STEEL	507.15	
15	11		26	GAL	WATER REPELLENT	514.10	
340	300		640	SY	SHEET MEMBRANE WATERPROOFING	519.20	
2	2		4	GAL	JOINT SEALER HOT POURED	524.10	
100	90		190	LF	JOINT SEALER, PREFORMED NEOPRENE	524.15	
1	1		2	GAL	JOINT SEALER, POLYURETHANE	524.20	
0.50	0.50		1	LS	MAINTENANCE OF TRAFFIC FOR BRIDGE PROJECTS	527.10	
360	320		680	SY	REMOVAL OF BRIDGE PAVEMENT	529.10	
3	3		6	CY	REMOVAL OF CONC. OR MASONRY (MOD)	529.25	
		10	10	HR	ALL PURPOSE EXCAVATOR RENTAL	608.25	
		10	10	HR	POWER BROOM RENTAL	608.30	
180			180	LF	REMOVING AND RESETTING CURB	616.40	
50	40	160	250	HR	UNIFORMED TRAFFIC OFFICERS	630.10	5
150	130	170	450	HR	FLAGGERS	630.15	15
0.50	0.50		1	LS	FIELD TESTING	631.15	
0.33	0.33	0.34	1	LS	MOBILIZATION	635.10	
180		300	480	LF	PAINTED CURB	646.21	25
		320	320	LF	DURABLE 4" WHITE LINE	646.30	
320		1000	1320	LF	DURABLE 4" YELLOW LINE	646.31	
		125	125	LF	DURABLE 8" YELLOW LINE	646.35	5
40		50	90	LF	DURABLE 24" STOP BAR	646.40	2
		3	3	EA	DURABLE ARROW MARKINGS	646.42	
4		28	32	EA	DURABLE LETTER IN WORD MARKINGS	646.44	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		LUDLOW VT 103 F 025-1(29)S
		BITUMINOUS CONC. PAVEMENT
479	TON	LEVEL
1405		WEARING
1170		SHOULDERS
100		DRIVE AND APPROACHES
26		ROUNDING
3180		TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS
TOTALS									

PROJECT NAME Ludlow, Mt. Holly
PROJECT NUMBER F-DECK(22)S, F025-1(29)S