

# QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	UTILITIES - BID ITEMS	BRIDGE NO. 1 (SHEET PILE WALL)	BRIDGE NO. 2 (GROUND ANCHORED)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
		175						175		LF	MISCELLANEOUS FENCE (WOOD POST AND RAIL)	620.80	4					
18.75								18.75		LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20	-					
1289								1289		LF	CONCRETE MEDIAN BARRIER (MOD.)	621.45	-					
1								1		EACH	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-					
1								1		EACH	TERMINAL CONNECTOR FOR STEEL BEAM GUARD RAIL	621.53	-					
30								30		LF	REMOVING AND RESET GUARD RAIL	621.75	7					
1020								1020		LF	REMOVL AND DISP OF GUARD RAIL	621.80	15					
11								11		EACH	REMOVL AND DISP OF GUIDE POSTS	621.81	-					
1.5								1.5		MFBM	INSULATION BOARD	622.10	4					
				1200				1200		LF	PVC SEWER PIPE (6")	628.35	34					
				520				520		LF	PVC SEWER PIPE (8")	628.35	8					
				90				90		LF	PVC SEWER PIPE (10")	628.35	4					
				3900				3900		LF	PVC SEWER PIPE (15")	628.35	36					
				1				1		LS	TRANSFER TO NEW SYSTEM-SANITARY SEWER	628.42	-					
				2				2		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-					
				1190				1190		LF	SEAMLESS COPPER WATER TUBE (3/4")	629.23	20					
				120				120		LF	SEAMLESS COPPER WATER TUBE (1")	629.23	14					
				90				90		LF	SEAMLESS COPPER WATER TUBE (1 1/2")	629.23	6					
				75				75		LF	SEAMLESS COPPER WATER TUBE (2")	629.23	7					
				60				60		LF	DUCTILE, IRON PIPE, CEM LINED (4")	629.24	10					
				275				275		LF	DUCTILE, IRON PIPE, CEM LINED (6")	629.24	5					
				925				925		LF	DUCTILE, IRON PIPE, CEM LINED (8")	629.24	9					
				160				160		LF	DUCTILE, IRON PIPE, CEM LINED (10")	629.24	6					
				4100				4100		LF	DUCTILE, IRON PIPE, CEM LINED (12")	629.24	108					
				23				23		EACH	EXTENSION SERVICE BOX AND CURB STOP (3/4")	629.25	-					
				3				3		EACH	EXTENSION SERVICE BOX AND CURB STOP (1")	629.25	-					
				3				3		EACH	EXTENSION SERVICE BOX AND CURB STOP (1 1/2")	629.25	-					
				1				1		EACH	EXTENSION SERVICE BOX AND CURB STOP (2")	629.25	-					
				1				1		EACH	GATE VALVE WITH VALVE BOX (4")	629.27	-					
				11				11		EACH	GATE VALVE WITH VALVE BOX (6")	629.27	-					
				13				13		EACH	GATE VALVE WITH VALVE BOX (8")	629.27	-					
				4				4		EACH	GATE VALVE WITH VALVE BOX (10")	629.27	-					
				28				28		EACH	GATE VALVE WITH VALVE BOX (12")	629.27	-					
				11				11		EACH	HYDRANT	629.28	-					
				4				4		EACH	HYDRANT (MOD. - YARD HYDRANT)	629.28	-					
				6				6		EACH	HYDRANT, REMOVE	629.30	-					
				4				4		EACH	METER PIT (MOD.)	629.31	-					
				15500				15500		LB	DUCTILE IRON FITTINGS	629.38	870					
				31				31		EACH	CORPORATION STOP (3/4")	629.39	-					
				3				3		EACH	CORPORATION STOP (1")	629.39	-					

PROJECT NAME: **HARTFORD**  
PROJECT NUMBER: **RS0113 (40)**  
FILE NAME: z86c027quant.xls PLOT DATE: 02/28/2007  
PROJECT MANAGER: KEN UPMAL, PE DRAWN BY: E. ATKINS  
DESIGNED BY: E. ATKINS CHECKED BY: KO ISHIKURA  
QUANTITY SHEET #4 SHEET 8 OF 239